

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	15	15					44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	40	40					
25200110	SODDING, SALT TOLERANT	SO YD	15	15					44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	40	40					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6					60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6, 12	FOOT	176	176					
40600300	AGGREGATE (PRIME COAT)	TON	30	30					60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	348	348					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	12					66000450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4, 75, N50	TON	312	312					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					67100100	MOBILIZATION	L SUM	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	149	149					70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	728	728					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
42001300	PROTECTIVE COAT	SO YD	94	94					70300100	SHORT TERM PAVEMENT MARKING	FOOT	1053	1053					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	224	224					70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	73	73					
42400800	DETECTABLE WARNING	SO FT	24	24					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3083	3083					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	7426	7426					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	534	534					
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	180	180					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	198	198					
									70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	70	70					

FILE NAME *	USER NAME * bauer/d	DESIGNED -	REVISED -
C:\p\work\concrete\4400159\160509-stl-sched.dgn		DRAWN -	REVISED -
PLOT SCALE * 100/0000 * / 1A		CHECKED -	REVISED -
PLOT DATE * 6/7/2012		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 43 (HARLEM AVE.) 39TH ST. (PERSING RD.) TO 40TH PL.
SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	430X-R	COOK	20	3
CONTRACT NO. 60T14				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

Rev. 10-29-12