

URBAN

100% STATE

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021					
35400450	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9-1/2"	SO YD	✓ 64	64					
20800150	TRENCH BACKFILL	CU YD	✓ 0.8	0.8					
30300112	AGGREGATE SUBGRATE IMPROVEMENT 12"	SO YD	✓ 64	64					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	60	60					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	75	75					
44000100	PAVEMENT REMOVAL	SO YD	99	99					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	76	76					
44001980	CONCRETE BARRIER REMOVAL	FOOT	20	20					
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	6	6					
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	1					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	125	125					
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	116	116					
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	60	60					
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1					
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1					

URBAN

100% STATE

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021					
63200310	GUARDRAIL REMOVAL	FOOT	53	53					
66400505	CHAIN LINK FENCE, 8'	FOOT	83	83					
66409400	CHAIN LINK GATES, 8' X 12' DOUBLE	EACH	1	1					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
* 72000100	SIGN PANEL - TYPE 1	SO FT	92	92					
* 78200410	GUARDRAIL MARKER, TYPE A	EACH	6	6					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1					
X0325207	TELEVISION INSPECTION OF SEWER	FOOT	9251	9251					
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	469	469					
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	1537	1537					
X5537900	STORM SEWERS TO BE CLEANED 15"	FOOT	1611	1611					
X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	1112	1112					
X5538200	STORM SEWERS TO BE CLEANED 24"	FOOT	290	290					
X7240195	REMOVE EXISTING SIGN PANEL	EACH	45	45					
20013798	CONSTRUCTION LAYOUT	L SUM	1	1					
20018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1					
20030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					

*Specialty Items