

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				IL 38 AT I-355 SB RAMPS	IL 38 AT I-355 NB RAMPS	90% FED 10% STATE	100% VILLAGE OF GLEN ELLYN
				TRAFFIC SIGNALS	TRAFFIC SIGNALS	INTERCONNECT	EVP
				0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	293	148	145		
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	1,230	646	584		
81400100	HANDHOLE	EACH	9	4	5		
81400200	HEAVY-DUTY HANDHOLE	EACH	6	3	3		
81400300	DOUBLE HANDHOLE	EACH	6	4	2		
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1			1	
86400100	TRANSCEIVER - FIBER OPTIC	EACH	2	1	1		
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	632			632	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,523				1,523
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	7,955	4,031	3,924		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	924	742	182		
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	10,796	4,558	6,238		
87301790	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 2 2 C	FOOT	642		642		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	70	70			

* SPECIALTY ITEMS

FILE NAME *	USER NAME *	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 2 OF 5)				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pvidat\pociechal\0806285\01	1112-shl-TS.dgn	DRAWN -	REVISED -		SCALE: NONE	SHEET NO.	OF	SHEETS	STA.	TO STA.	347	32	4
	PLOT SCALE * 100.0000' / in.	CHECKED -	REVISED -										
	PLOT DATE * 8/13/2012	DATE -	REVISED -										
											CONTRACT NO. 60179		
[ILLINOIS] FED. AID PROJECT													