



**NOTES**

1. THE EXISTING FIBER OPTIC AND TRACER CABLE FROM BAKER HILL DR TO I-355 RAMP "A" AND "C" SHALL BE PULLED BACK TO THE FAR OUT HANDHOLE ON THE WEST LEG ALONG IL RTE 38 (APPROX. STA. 725+40) AND STORED IN IT FOR REUSE ON THE PROPOSED INTERCONNECT. THIS WORK WILL BE PAID FOR AS REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT.
2. THE FIBER OPTIC AND TRACER CABLE SHALL BE STORED AND PROTECTED DURING CONSTRUCTION. THE CONTRACTOR WILL BE RESPONSIBLE FOR ANY DAMAGE AND WILL BE REQUIRED TO REPLACE ANY DAMAGED CABLE AT NO ADDITIONAL COST TO THE CONTRACT.
3. TEMPORARY RADIO INTERCONNECT ANTENNA AT THE INTERSECTION OF IL RTE 38 AND BAKER HILL DR SHALL BE INSTALLED ON THE MAST ARM ASSEMBLY AND POLE AS SHOWN. THE CABLE FROM THE ANTENNA SHALL BE INSTALLED IN THE EXISTING CONDUITS BETWEEN THE ANTENNA AND THE EXISTING CONTROLLER. THE ANTENNA AND ALL CABLES SHALL BE REMOVED UPON COMPLETION OF THE PROPOSED FIBER OPTIC INTERCONNECT SYSTEM. ANY HOLES IN THE MAST ARM SHALL BE PLUGGED. THIS WORK SHALL BE INCLUDED IN THE TEMPORARY TRAFFIC SIGNAL INSTALLATION.

**RESTORATION OF WORK AREA.** RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCLUDED IN THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIAN, SIDEWALKS, PAVEMENT ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

**NOTE:** THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

FILE NAME =	USER NAME = poc1echal	DESIGNED - LP / PB	REVISED -
et:\pw_work\p1dot\poc1echal\10386285\104112-sht-TS.dgn	4112-sht-TS.dgn	DRAWN - LP / PB	REVISED -
Default	PLOT SCALE = 100.0000' / in.	CHECKED - SM	REVISED -
	PLOT DATE = 8/13/2012	DATE - 07/26/12	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>TEMPORARY INTERCONNECT PLAN AND SCHEMATIC</b>			
<b>IL RTE 38 (BAKER HILL DR TO I-355 NB RAMP)</b>			
SCALE: 1"=50'	SHEET	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
347	CY-TS-1 (12)	DUPAGE	32	26
<b>CONTRACT NO. 60T79</b>				
ILLINOIS FED. AID PROJECT				