

URBAN

LSSEV, 01

07POY, 01

SUMMARY OF QUANTITIES		CONSTRUCTION CODE										
		LOCATION OF WORK	DEMPSTER STREET AT BUSSE ROAD	IL 62 (ALGONQUIN RD) AT BUSSE ROAD	IL 62 (ALGONQUIN RD) AT DEMPSTER STREET	INTERCONNECT	EMERGENCY VEHICLE PREEMPTION	FUNDING BREAKDOWNS				
								90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	100% VILLAGE OF MOUNT PROSPECT
								TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	INTERCONNECT	TRAFFIC SIGNALS
TYPE	0021	0021	0021	0021	0021	0021						
CODE NO.	ITEM	UNIT	TOTAL	URBAN	URBAN	URBAN	URBAN	URBAN				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,095	765	110	220						
⚠ 20101000	TEMPORARY FENCE	FOOT	75	25	50							
42400800	DETECTABLE WARNINGS	SQ FT	28	28								
⚠ 20101200	TREE ROOT PRUNING	EACH	3	1	2							
44000600	SIDEWALK REMOVAL	SQ FT	1,095	765	110	220						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5.00	1.50	1.50	1.50	0.50					
67100100	MOBILIZATION	L SUM	1.00	0.30	0.30	0.30	0.10					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1.00	0.30	0.30	0.30	0.10					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.00	0.30	0.30	0.30	0.10					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.00	0.30	0.30	0.30	0.10					
* 72000100	SGN PANEL - TYPE 1	SQ FT	63.00	31.50	13.50	18.00						
* 72000200	SGN PANEL - TYPE 2	SQ FT	25.00		25.00							
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	3.00	1.00	1.00	1.00						
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1,480	489	265	258	468					
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	420	102	243	75						
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	200	38	111	53						

* SPECIALTY ITEM

FILE NAME = 4385-882-TRI.dwg



USER NAME = ZACH WALLSTEN
 PLOT SCALE = 1" = 60.33'
 PLOT DATE = 8/15/2012

DESIGNED - JRD
 DRAWN - ZCW
 CHECKED - KLB
 DATE - 8/15/2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 (SHEET 1 OF 6)

SCALE N.A. SHEET NO. OF SHEETS STA TO STA.

F.A.P. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	2012-030TS	COOK	39	3
CONTRACT #:			60T82	
ILLINOIS FED. AID PROJECT				

Rev. 10-25-12

GHA #4085.882