

SUMMARY OF QUANTITIES		CONSTRUCTION CODE						
		LOCATION OF WORK	DEMPSTER STREET AT BUSSE ROAD	IL 62 (ALGONQUIN RD) AT BUSSE ROAD	IL 62 (ALGONQUIN RD) AT DEMPSTER STREET	INTERCONNECT	EMERGENCY VEHICLE PREEMPTION	
		FUNDING BREAKDOWNS	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	90% FEDERAL 10% STATE	100% VILLAGE OF MOUNT PROSPECT	
		TYPE	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	INTERCONNECT	TRAFFIC SIGNALS	
CODE NO.	ITEM	UNIT	TOTAL	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN
88800100	PEDESTRIAN PUSH-BUTTON	EACH	22	9	9	4		
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1				
89500120	REMOVE EXISTING SERVICE INSTALLATION	EACH	1	1				
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	8,693	1,328	1,874	1,601	3,890	
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	3	1	1	1		
89502380	REMOVE EXISTING HANDHOLE	EACH	26	7	10	9		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	24	8	8	8		
X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	3,482	540	784	417		1,741
X0324599	ROD AND CLEAN EXISTING CONDUIT	FOOT	4,163	664	937	617	1,945	
<b>XX000406</b>	<b>BRICK PAVER REMOVAL AND REPLACEMENT</b>	SQ FT	900		900			
X8100105	CONDUIT SPLICE	EACH	16	5	8	3		
X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2	1		1		
X8570231	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1		1			
X8800105	MASTER CONTROLLER (SPECIAL)	EACH	1		1			

\* SPECIALTY ITEM

FILE NAME = 4085.882-TR1.dwg

<b>GHA</b> GEWALT HAMILTON ASSOCIATES, INC.	USER NAME = ZACH WALLSTEN	DESIGNED - JRD	REVISED -
	PLOT SCALE = 1" = .0833'	DRAWN - ZCW	REVISED -
	PLOT DATE = 8/15/2012	CHECKED - KLB	REVISED -
		DATE - 8/15/2012	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES (SHEET 5 OF 6)</b>			
SCALE N.A.	SHEET NO. OF SHEETS	STA. TO STA.	

E.A.P. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-	2012-030TS	COOK	39	7
CONTRACT #:			60T82	
ILLINOIS FED. AID PROJECT				

Rev. 10-25-12

GHA #4085.882