

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LAWRENCE ROAD		
				ROADWAY 0004	BRIDGE REPLACEMENT 0011	MCHENRY COUNTY (NON-PARTICIPATING)
20101000	TEMPORARY FENCE	FOOT	25	25		
20200100	EARTH EXCAVATION	CU YD	2,329	2,329		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,509	2,509		
20300100	CHANNEL EXCAVATION	CU YD	216	216		
20400800	FURNISHED EXCAVATION	CU YD	2,492	2,492		
20800150	TRENCH BACKFILL	CU YD	444	444		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6,410	6,410		
25000210	SEEDING, CLASS 2A	ACRE	0.59	0.59		
25000310	SEEDING, CLASS 4	ACRE	0.74	0.74		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	121	121		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	121	121		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	121	121		
25100630	EROSION CONTROL BLANKET	SQ YD	5,900	5,900		
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	453	453		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	134	134		
28000305	TEMPORARY DITCH CHECKS	FOOT	228	228		
28000400	PERIMETER EROSION BARRIER	FOOT	2,204	2,204		
28000500	INLET AND PIPE PROTECTION	EACH	6	6		
28100107	STONE RIPRAP, CLASS A4	SQ YD	731	211	520	
28200200	FILTER FABRIC	SQ YD	731	211	520	
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	2,018	2,018		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,081	1,081		
40600300	AGGREGATE (PRIME COAT)	TON	7	7		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	24	24		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	142	142		
40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	1,850	1,850		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	144	144		
44000100	PAVEMENT REMOVAL	SQ YD	2,032	2,032		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,660	1,660		
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	374	374		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,429	1,429		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50105220	PIPE CULVERT REMOVAL	FOOT	164	164		
50200100	STRUCTURE EXCAVATION	CU YD	204		204	
50300225	CONCRETE STRUCTURES	CU YD	108.6		108.6	

\* SPECIALTY ITEMS

FILE NAME: M:\795-02 Lawrence Phase II\CADD SHEETS\795-012-11t-500.dgn



USER NAME = gollwanger  
 PLOT SCALE = 20.0000' / 1" =  
 PLOT DATE = 10/23/2012

DESIGNED - GJE  
 DRAWN - GJE  
 CHECKED - CF  
 DATE - 08/17/12

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**MCHENRY COUNTY  
 DIVISION OF TRANSPORTATION**

**LAWRENCE ROAD BRIDGE OVER PISCASAW CREEK  
 SUMMARY OF QUANTITIES**

SCALE: NONE    SHEET NO. 3 OF 87 SHEETS    STA.    TO STA.

F.A.S. RTE. 0028	SECTION 08-00355-01-BR	COUNTY MCHENRY	TOTAL SHEETS 87	SHEET NO. 3
				CONTRACT NO. 63694
ILLINOIS FED. AID PROJECT				