

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LAWRENCE ROAD		
				ROADWAY 0004	BRIDGE REPLACEMENT 0011	MCHENRY COUNTY (NON-PARTICIPATING)
50300255	CONCRETE SUPERSTRUCTURE	CU YD	156.3		156.3	
50300260	BRIDGE DECK GROOVING	SQ YD	648		648	
50300280	CONCRETE ENCASEMENT	CU YD	21.6		21.6	
50300300	PROTECTIVE COAT	SQ YD	773		773	
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	3,986		3,986	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	52,120		52,120	
50800515	BAR SPLICERS	EACH	354		354	
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	1,400		1,400	
51202305	DRIVING PILES	FOOT	1,400		1,400	
51203200	TEST PILE METAL SHELLS	EACH	4		4	
51500100	NAME PLATES	EACH	1		1	
51603000	DRILLED SHAFT IN SOIL	CU YD	2			2
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4	4		
542A0277	PIPE CULVERTS, CLASS A, TYPE 1 72"	FOOT	180	180		
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	107	107		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	127		127	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	238	238		
* 63000360	LONG-SPAN GUARDRAIL OVER CULVERT, 18 FT 9 IN SPAN	FOOT	169	169		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
63200310	GUARDRAIL REMOVAL	FOOT	94	94		
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2		
* 66400305	CHAIN LINK FENCE, 6'	FOOT	16			16
* 66401900	CHAIN LINK GATES, 5' X 6' SINGLE	EACH	2			2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7		
67100100	MOBILIZATION	L SUM	1	1		
* 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	6	6		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	9	9		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5,248	5,248		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	46	46		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,794	1,794		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	460	460		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	460	460		
72000100	SIGN PANEL - TYPE 1	SQ FT	24	24		
72900100	METAL POST - TYPE A	FOOT	20	20		
72900200	METAL POST - TYPE B	FOOT	32	32		

* SPECIALTY ITEMS

FILE NAME = W:\755-012 Lawrence Plaza IL\ROAD SHEETS\755-012-01-300.dgn



USER NAME = gellinger
 PLOT SCALE = 20.0000 / 1" = 100'
 PLOT DATE = 8/17/2012

DESIGNED - GJE
 DRAWN - GJE
 CHECKED - CF
 DATE - 08/17/12

REVISED -
 REVISED -
 REVISED -
 REVISED -

**MCHENRY COUNTY
 DIVISION OF TRANSPORTATION**

**LAWRENCE ROAD BRIDGE OVER PISCASAW CREEK
 SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. 4 OF 87 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0028	08-00355-01-BR	MCHENRY	87	4
			CONTRACT NO. 63694	
ILLINOIS FED. AID PROJECT				