

SIDEWALK SCHEDULE

STATION BEGIN	STATION END	4400800	42400800	X4240430	35101582	XX004888	XX008277	31101400
		SIDEWALK REMOVAL	DETECTABLE WARNINGS	PCC SIDEWALK 5 INCH, SPECIAL	AGGREGATE BASE COURSE TYPE B, 2"	BRICK PAVER SIDEWALK	PCC UNDERLAYMENT 5 INCH	GRANULAR MATERIAL TYPE B, 6"
		SQ FT	SQ FT	SQ FT	SQ YD	SQ FT	SQ YD	SQ YD
10+95 RT	18+07 RT (KNOX AVE)	3,911	24	4,960	553	1,309	145	145
11+10 LT	11+54 LT (KEATING AVE)	142	8	163	18	21	2	2
11+54 LT (KEATING AVE)	14+81 LT (KILPATRICK AVE)	1,575	16	1,790	199	272	30	30
14+81 LT (KILPATRICK AVE)	18+07 LT (KNOX AVE)	2,853	24	3,170	352	554	62	62
18+07 RT (KNOX AVE)	21+37 RT (KENTON AVE)	1,977	32	2,460	273	534	59	59
18+07 LT (KNOX AVE)	21+37 LT (KENTON AVE)	2,338	32	2,466	274	371	41	41
21+37 RT (KENTON AVE)	24+65 RT (KOLMAR AVE)	2,119	32	2,542	282	478	53	53
21+37 LT (KENTON AVE)	24+65 LT (KOLMAR AVE)	2,803	32	3,193	355	458	51	51
24+65 RT (KOLMAR AVE)	27+92 RT (KILBOURNE AVE)	2,204	32	2,647	294	461	51	51
24+65 LT (KOLMAR AVE)	27+92 LT (KILBOURNE AVE)	2,890	32	3,289	367	465	52	52
27+92 RT (KILBOURNE AVE)	31+20 RT (KENNETH AVE)	2,666	32	3,088	344	524	58	58
27+92 LT (KILBOURNE AVE)	31+20 LT (KENNETH AVE)	2,703	32	3,116	346	464	52	52
31+20 RT (KENNETH AVE)	34+48 RT (KOSTNER AVE)	1,891	32	2,300	256	430	48	48
31+20 LT (KENNETH AVE)	34+48 LT (KOSTNER AVE)	1,694	32	2,344	260	649	72	72
34+48 RT (KOSTNER AVE)	37+58 RT	2,167	32	2,722	302	538	60	60
34+48 LT (KOSTNER AVE)	37+80 LT	2,032	32	2,387	265	437	49	49
TOTAL		35,965	456	42,677	4,742	7,966	885	885

DESIGNED BY: JAVIER S. RODRIGUEZ
 DRAWN BY: JAVIER S. RODRIGUEZ
 CHECKED BY: MOW
 DATE: 5-14-12
 REVISED BY: MOW
 DATE: 5-14-12
 FILE: 100751 Schedule.sh



DESIGNED - DSH	REVISED - 8-3-12 PER 100T
DRAWN - MAC	REVISED -
CHECKED - MOW	REVISED -
DATE - 5-14-12	FILE - 100751 Schedule.sh

VILLAGE OF SKOKIE, ILLINOIS
F.A.U. ROUTE 1332 E. OAKTON STREET
FROM F.A.P. 350 U.S. ROUTE 41 (SKOKIE BOULEVARD) TO LOWELL AVENUE
STREETSCAPE IMPROVEMENTS

SCHEDULE OF QUANTITIES	
SCALE: NONE	STA. TO STA.

F.A.U. RTE. 1332	SECTION 11-00286-00-LS	COUNTY COOK	TOTAL SHEETS 29	SHEET NO. 9
C-91-149-12		CONTRACT NO. 63737		FED. AID PROJECT TE-0001(889)