SPECIALTY ITEM	CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	0004	0021	0021	0031	0043	0031
					RECONSTRUCTION, NO CAPACITY ADDED	SAFETY (SW / BP)	SAFETY (LIGHTING)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	UTILITIES (NON-PARTICIPATING)	NON-PARTICIPATING
	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	14108	14108					
	31101180	SUBBASE GRANULAR MATERIAL, TYPE B 2"	SQ YD	2865	615	2250				
	31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	343	343					
	31101500	SUBBASE GRANULAR MATERIAL, TYPE B 7"	SQ YD	773	773					
	31101810	SUBBASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	6		6				
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7502	7502					
	40600300	AGGREGATE (PRIME COAT)	TON	25	25					
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
	40701861	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9"	SQ YD	12503	12503					
	42001200	PAVEMENT FABRIC	SQ YD	836	773					63
	42001300	PROTECTIVE COAT	SQ YD	4946	2684	2222				40
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	773	773					
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	19996		19996				
	42400800	DETECTABLE WARNINGS	SQ FT	528		528				
	44000100	PAVEMENT REMOVAL	SQ YD	16877	14848					2029
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	295	295					
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5266	5266					
	44000600	SIDEWALK REMOVAL	SQ FT	18562	18562					
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	66	66					
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	277	277					
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	135	135					
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	648	648					
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	331	331					

X DENOTES SPECIALTY ITEM

FILE NAME = ...\2536_S09.dgn	USER NAME = djk	DESIGNED - JAT	REVISED -
		DRAWN - JAT	REVISED -
	PLOT SCALE = 20.0000 ' / in.	CHECKED - DJK	REVISED -
	PLOT DATE = 8/15/2012	DATE - 8/20/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WALNUT LANE
SUMMARY OF QUANTITIES

SHEET NO. 2 OF 8 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2556	08-00094-00-PV	COOK	113	5

CONTRACT NO. 63738

(ILLINOIS FED. AID PROJECT M-9003(494))

PLAN — NOTE BOOK NO. ____ — SURVEYED / PLOTTED / ALIGNMENT CHECKED / RT. OF WAY CHECKED / CADD FILE NAME — BY — DATE

PROFILE — NOTE BOOK NO. ____ — SURVEYED / PLOTTED / GRADES CHECKED / B.M. NOTED / STRUCTURE NOTATIONS CHKD — BY — DATE