SPECIALTY ITEM	CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	0004	0021	0021	0031	0043	0031
					RECONSTRUCTION, NO CAPACITY ADDED	SAFETY (SW / BP)	SAFETY (LIGHTING)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	UTILITIES (NON-PARTICIPATING)	NON-PARTICIPATING
	60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	5	5					
	60207915	CATCH BASINS, TYPE C, TYPE 11V FRAME AND GRATE	EACH	12	12					
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	7					
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4					
	60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1					
	60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	4	4					
	60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	3	3					
	60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	1	1					
	60255500	MANHOLES TO BE ADJUSTED	EACH	5	5					
X	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1					
	60500040	REMOVING MANHOLES	EACH	3	3					
	60500050	REMOVING CATCH BASINS	EACH	3	3					
	60500060	REMOVING INLETS	EACH	14	14					
	60600605	CONCRETE CURB, TYPE B	FOOT	14	14					
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	4754	4754					
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1204	1204					
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	134	134					
	60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	132	132					
	60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	80	80					
	60624600	CORRUGATED MEDIAN	SQ FT	95	95					
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12					
	67100100	MOBILIZATION	L SUM	1	1					

X DENOTES SPECIALTY ITEM

PLAN — NOTE BOOK NO. — SURVEYED — PLOTTED — ALIGNMENT CHECKED — RT. OF WAY CHECKED — CADD FILE NAME — BY — DATE

PROFILE — NOTE BOOK NO. — SURVEYED — PLOTTED — GRADES CHECKED — B.M. NOTED — STRUCTURE NOTATIONS CHKD — BY — DATE

FILE NAME = ...\2536.SDQ.dgn	USER NAME = djk	DESIGNED - JAT	REVISED -
		DRAWN - JAT	REVISED -
	PLOT SCALE = 20.0000 ' / in.	CHECKED - DJK	REVISED -
	PLOT DATE = 8/15/2012	DATE - 8/20/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WALNUT LANE
SUMMARY OF QUANTITIES

SHEET NO. 4 OF 8 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2556	08-00094-00-PV	COOK	113	7

CONTRACT NO. 63738

ILLINOIS FED. AID PROJECT M-9003(494)