SPECIALTY ITEM	CODED PAY ITEM NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	0004	0021	0021	0031	0043	0031
					RECONSTRUCTION, NO CAPACITY ADDED	SAFETY (SW / BP)	SAFETY (LIGHTING)	LANDSCAPING AND OTHER SCENIC BEAUTIFICATION	UTILITIES (NON-PARTICIPATING)	NON-PARTICIPATING
X	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	171			171			
X	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	48			48			
X	81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	195			195			
X	82102150	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 150 WATT	EACH	3			3			
X	82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	1			1			
X	83000198	LIGHT POLE, ALUMINUM, 25 FT. M.H., 10 FT. MAST ARM	EACH	3			3			
X	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	22			22			
X	83600352	LIGHT POLE FOUNDATION, METAL, 11 1/2" BOLT CIRCLE, 8 5/8" X 6'	EACH	2			2			
X	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1			1			
X	84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1			1			
X	84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1			1			
X	87602000	PEDESTRIAN PUSH-BUTTON POST	EACH	2	2					
X	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1760			1760			
X	A2000120	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	4				4		
X	A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2				2		
X	A2004520	TREE, GINKGO BILOBA PRINCETON SENTRY (PRINCETON SENTRY GINKGO), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2				2		
X	A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2				2		
X	A2008517	TREE, ULMUS JAPONICA X WILSONIANA MORTON (ACCOLADE ELM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3				3		
X	B2006320	TREE, SYRINGA RETICULATA IVORY SILK (IVORY SILK JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	6				6		
X	C2003424	SHRUB, HYDRANGEA ARBORESCENS ANNABELLE (ANNABELLE SMOOTH HYDRANGEA), 2' HEIGHT, BALLED AND BURLAPPED	EACH	8						8
X	C2C078G3	SHRUB, ROSA X KNOCK OUT (KNOCK OUT ROSE), CONTAINER GROWN, 3-GALLON	EACH	10						10
X	K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	70						70
X	K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	5						5

X DENOTES SPECIALTY ITEM

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / BY / DATE / NOTE BOOK / BLM NOTED / STA. OF MAT'L CHECKED / NO. / CADD FILE NAME

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / BY / DATE / NOTE BOOK / BLM NOTED / STRUCTURE NOTATIONS CHKD / NO.

FILE NAME = ...\2836_S00.dgn	USER NAME = djk	DESIGNED - JAT	REVISED -
		DRAWN - JAT	REVISED -
	PLOT SCALE = 20.0000 ' / in.	CHECKED - DJK	REVISED -
	PLOT DATE = 8/15/2012	DATE - 8/20/2012	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WALNUT LANE
SUMMARY OF QUANTITIES

SHEET NO. 6 OF 8 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2556	08-00094-00-PV	COOK	113	9

CONTRACT NO. 63738

ILLINOIS FED. AID PROJECT M-9003(494)