	SUMMARY OF QUANTITIES		CONSTRUCTION TYPE CODE 0005
CODE NUMBER	DESCRIPTION	UNITS	TOTAL QUANTITY
20101200	TREE ROOT PRUNING	EACH	6
28000510	INLET FILTERS	EACH	73
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	229
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7,946
40600300	AGGREGATE (PRIME COAT)	TON	156
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,636
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	382
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3,276
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2,943
42400800	DETECTABLE WARNINGS	SQ FT	580
44000600	SIDEWALK REMOVAL	SQ FT	2,717
44200901	CLASS B PATCHES, TYPE I, 6 INCH	SQ YD	4
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	8
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	14
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	32
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	3,348
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2
60255500	MANHOLES TO BE ADJUSTED	EACH	19
60260100	INLETS TO BE ADJUSTED	EACH	36
60266600	VALVE BOXES TO BE ADJUSTED	EACH	3
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	8
60500060	REMOVING INLETS	EACH	4
60608562	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	20
67100100	MOBILIZATION	L SUM	1
# 70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
# 70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
# 70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3,126
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	521
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	42
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5,117

* DENOTES SPECIALTY ITEM

# DENOTES ITEMS COVERED BY SPECIAL PROVISION

	SUMMARY OF QUANTITIES		CONSTRUCTION TYPE CODE 0005
CODE NUMBER	DESCRIPTION	UNITS	TOTAL QUANTITY
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,544
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	808
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	351
* # 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
* # 88600100	DETECTOR LOOP, TYPE 1	FOOT	85
# X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	38,069
# X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	12
# X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1
# XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	384
# XX007278	PARKWAY RESTORATION	SQ YD	6,017
# Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	360
# Z0004514	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 4"	SQ YD	1,463
# Z0004544	HOT-MIX ASPHALT DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,463
# Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	16,771

* DENOTES SPECIALTY ITEM

# DENOTES ITEMS COVERED BY SPECIAL PROVISION

COPYRIGHT © 2012 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-000257 - EXPIRES 4/30/2013
8/27/2012 8:35:25 AM

BAXTER & WOODMAN Consulting Engineers

DESIGNED - BNP	REVISED -	
DRAWN - BCD	REVISED -	
CHECKED - TAO	REVISED -	
DATE - 08/21/12	FILE - 120499-SOQ.sht	

VILLAGE OF PARK FOREST, ILLINOIS
BLACKHAWK DRIVE
RESURFACING

SUMMARY OF QUANTITIES

SCALE: NONE | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1057	12-00097-00-RS	COOK-WILL	24	3

CONTRACT NO. 63740

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT M-4003(077)