

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0005 QUANTITY	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	50	50	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	95	95	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4	
25200100	SODDING	SQ YD	95	95	
25200200	SUPPLEMENTAL WATERING	UNIT	3	3	
# 30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	50	50	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	215	215	
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	116	116	
35800100	PREPARATION OF BASE	SQ YD	1,500	1,500	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	18	18	
40600300	AGGREGATE (PRIME COAT)	TON	63	63	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	5	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,086	1,086	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	370	370	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N60	TON	294	294	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,738	1,738	
42001300	PROTECTIVE COAT	SQ YD	115	115	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	720	720	
42400800	DETECTABLE WARNINGS	SQ FT	132	132	
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	5,800	5,800	
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	1,650	1,650	
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	5,370	5,370	
44000170	HOT-MIX ASPHALT SURFACE REMOVAL, 5 1/4"	SQ YD	1,500	1,500	
44000600	SIDEWALK REMOVAL	SQ FT	720	720	
44201690	CLASS D PATCHES, TYPE I, 4 INCH	SQ YD	24	24	
44201692	CLASS D PATCHES, TYPE II, 4 INCH	SQ YD	48	48	
44201694	CLASS D PATCHES, TYPE III, 4 INCH	SQ YD	72	72	
44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	90	90	
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	62	62	
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	124	124	
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	186	186	
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	248	248	
44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	53	53	

* INDICATES SPECIALTY ITEM
INDICATES SPECIAL PROVISION

SUMMARY OF QUANTITIES			URBAN
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	106
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	159
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	211
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	332
67100100	MOBILIZATION	L SUM	1
# 70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701305	L SUM	1
# 70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1
# 70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
# 70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,904
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	247
72000100	SIGN PANEL - TYPE 1	SQ FT	78
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	4
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	150
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	357
# 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14,744
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	768
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	105
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,554
* 78000850	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	88
78300100	PAVEMENT MARKING REMOVAL	SQ FT	30
# Z0003300	BASE COURSE REMOVAL (SPECIAL)	SQ YD	300
# Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	150
# Z0019600	DUST CONTROL WATERING	UNIT	175
# Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	156
# Z0053700	RESETTING SURVEY MONUMENTS	EACH	1
# X2020110	GRADING AND SHAPING SHOULDERS	UNIT	70
# X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4
# X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2

* INDICATES SPECIALTY ITEM
INDICATES SPECIAL PROVISION
\$ INDICATES CONSTRUCTION CODE 0042 TRAINEES

COPYRIGHT © 2012 BY BAKER & WOODMAN, INC. ...
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 06-0015875 EXP. 06/30/2015
 PROJECT NO. 110783-GENNOTES.dwg
 DATE 06/22/12



DESIGNED - MWP	REVISED - IDOT REVIEW 08-20-12
DRAWN - KAR	REVISED -
CHECKED - MWP	REVISED -
DATE - 06-22-12	FILE - 110783-GENNOTES.dwg

VILLAGE OF SOUTH ELGIN, ILLINOIS
McDONALD ROAD
STP IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A.P. RTE. 637	SECTION 12-00040-00-RS	COUNTY KANE	TOTAL SHEETS 21	SHEET NO. 4
FED. ROAD DIST. NO. C-91-296-12		ILLINOIS FED. AID PROJECT W-9003975		CONTRACT NO. 63741