

SUMMARY OF QUANTITIES					
CODE NO	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY RECONSTRUCTION CODE 004	TRAINEES CODE 0042
20100100	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	100.00	100.00	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	100.00	100.00	
20101100	TREE TRUNK PROTECTION	EACH	60.00	60.00	
20101200	TREE ROOT PRUNING	EACH	20.00	20.00	
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	100.00	100.00	
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	100.00	100.00	
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	100.00	100.00	
20200100	EARTH EXCAVATION	CU YD	3,545.00	3,545.00	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,000.00	1,000.00	
30300000	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	1,316.00	1,316.00	
30300104	AGGREGATE SUBGRADE IMPROVEMENT 4"	SQ YD	9,587.00	9,587.00	
20800150	TRENCH BACKFILL	CU YD	1,000.00	1,000.00	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	7,282.00	7,282.00	
25000100	SEEDING, CLASS 1	ACRE	1.50	1.50	
25200110	SODDING, SALT TOLERANT	SQ YD	8,333.00	8,333.00	
28000305	TEMPORARY DITCH CHECKS	FOOT	275.00	275.00	
28000400	PERIMETER EROSION BARRIER	FOOT	4,778.00	4,778.00	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200.00	200.00	
40500100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	3,500.00	3,500.00	
40800982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	350.00	350.00	
40803335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	100.00	100.00	
40701846	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/4"	SQ YD	7,950.00	7,950.00	
42400600	DETECTABLE WARNINGS	SQ FT	60.00	60.00	
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	6,100.00	6,100.00	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	100.00	100.00	
48101800	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	30.00	30.00	
50105220	PIPE CULVERT REMOVAL	FOOT	30.00	30.00	
54010805	PRECAST CONCRETE BOX CULVERTS 8' X 8'	FOOT	7.00	7.00	
54213857	PRECAST REINFORCED CONCRETE FLARED-END SECTIONS 12"	EACH	1.00	1.00	
54247080	GRATING FOR CONCRETE FLARED-END SECTION 12"	EACH	1.00	1.00	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	750.00	750.00	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	2,000.00	2,000.00	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	30.00	30.00	
60107600	PIPE UNDERDRAINS 4"	FOOT	60.00	60.00	
60200605	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1.00	1.00	
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	10.00	10.00	
60201110	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11V FRAME AND GRATE	EACH	2.00	2.00	
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	2.00	2.00	
60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	5.00	5.00	
60207915	CATCH BASINS, TYPE C, TYPE 11V FRAME AND GRATE	EACH	1.00	1.00	
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3.00	3.00	
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	8.00	8.00	
60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	3.00	3.00	
60504400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	5,000.00	5,000.00	
67100100	MOBILIZATION	L SUM	1.00	1.00	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4,760.00	4,760.00	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200.00	200.00	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	350.00	350.00	
* X6331009	REMOVE AND REPLACE STEEL PLATE BEAM GUARDRAIL, SPECIAL	FOOT	100.00	100.00	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.00	1.00	
Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	100.00	100.00	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	20.00	20.00	
Z0078600	TRAINEES	HOUR	500.00		500.00
Z0078604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500.00		500.00

* SPECIALTY ITEMS

FILE NAME =	USER NAME = \$USER\$	DESIGNED -	REVISED -
H:\11-PH\3004\PLANS-ENG\REV-1\11-PH-	004_SITE_2012-09-05.dwg	DRAWN -	REVISED -
	PLOT SCALE = \$SCALE\$	CHECKED -	REVISED -
	PLOT DATE = Sep 05, 2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

76TH AVENUE 131ST STREET TO 127TH STREET
SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. ___ OF ___ SHEETS STA. 27+71 TO STA. 52+61

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3791	08-00043-00-FP	COOK	27	3
CONTRACT NO. 63747			ILLINOIS FED. AID PROJECT	