


# SUMMARY OF QUANTITIES

CONSTRUCTION  
CODE  
80% FED  
20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	RECONSTRUCTION 0011 SN 081-2038
28200200	FILTER FABRIC	SQ YD	37	37
31100500	SUBBASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	174	174
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	752	752
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	75	75
40600990	TEMPORARY RAMP	SQ YD	39	39
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	127	127
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	5	5
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	174	174
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1,262	1,262
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	42,270	42,270
50800515	BAR SPLICERS	EACH	122	122
51500100	NAME PLATES	EACH	1	1
54003000	CONCRETE BOX CULVERTS	CU YD	134	134
54215553	METAL END SECTIONS 18"	EACH	4	4

+ SPECIALTY ITEM      ++ NON-PARTICIPATING 100% STATE

FILE NAME = S:\JUL162008-6399\6346.026\Micro\CAD00-Sheets\026-025-INT-5001.dgn



USER NAME = amondaj	DESIGNED -	REVISED -
PLLOT SCALE = 28.8900 1/1 in.	DRAWN -	REVISED -
PLLOT DATE = 0/15/2012	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES</b>			
SCALE: N/A	SHEET 2	OF 5 SHEETS	STA. TO STA.

F.A.P. RTE. 308	SECTION 110T	COUNTY ROCK ISLAND	TOTAL SHEETS 51	SHEET NO. 5
CONTRACT NO. 64925				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				