


SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE
				80% FED 20% STATE
				RECONSTRUCTION 0011 SN 081-2038
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	93	93
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4	4
60107600	PIPE UNDERDRAINS 4"	FOOT	140	140
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	1	1
+ 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	612.5	612.5
+ 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	75	75
+ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	454	454
+ 63500105	DELINEATORS	EACH	4	4
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	1,091	1,091
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1

+ SPECIALTY ITEM ++ NON-PARTICIPATING 100% STATE

FILE NAME : S:\JUL\15200 - 6799\6746\B26\Micro\6400_Sheet 3 of 5\B26\Q25.sht-5001.dgn



USER NAME : amanda_j	DESIGNED -	REVISED -
PLOT SCALE : 20,0000' / in.	DRAWN -	REVISED -
PLOT DATE : 8/15/2012	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N/A	SHEET 3	OF 5 SHEETS	STA. TO STA.

F.A.P. RTE. 308	SECTION 110T	COUNTY ROCK ISLAND	TOTAL SHEETS 51	SHEET NO. 6
CONTRACT NO. 64925				
FED. ROAD DIST. NO. 2 [ILLINOIS] FED. AID PROJECT				