


80% FED.
20% STATE

SUMMARY OF QUANTITIES				
CONSTRUCTION CODE TYPE:			TOTAL	0011
CODE NO.	ITEM	UNIT	QUANTITY	SN 050-0183 (EX) SN 050-2054 (PR)
50800105	REINFORCEMENT BARS	POUND	8,450	8,450
51500100	NAME PLATES	EACH	1	1
54003000	CONCRETE BOX CULVERTS	CU YD	55.4	55.4
54010905	PRECAST CONCRETE BOX CULVERTS 9' X 5'	FOOT	108	108
54201063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	84	84
54215553	METAL END SECTIONS 18"	EACH	2	2
63200310	GUARDRAIL REMOVAL	FOOT	460	460
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, <i>STANDARD T01406</i>	L SUM	1	1
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	740	740
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	93	93
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4	4

*SPECIALTY ITEMS

FILE NAME *	USER NAME * #USER*	DESIGNED - RAC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	 <small>Zroka Engineering, P.C. 4216 North Hermitage Chicago, IL 60613</small>	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILE#		DRAWN - RAC	REVISED -				623	(H)BR-1	LASALLE	32	5
PLOT SCALE * #SCALE*		CHECKED - DAZ	REVISED -				CONTRACT NO. 66A13				
PLOT DATE * #DATE*		DATE - 08/10/12	REVISED -				ILLINOIS FED. AID PROJECT				
				SCALE: N/A	SHEET NO. 3 OF 4 SHEETS						

Rev