



BAR LIST

BAR NO.	SIZE	LENGTH	SHAPE
n1	#5	21'-0"	U
n2	#4	21'-0"	U
n3	#4	28'-0"	U
n4	#5	5'-6"	U
n5	#5	8'-6"	U
n6	#4	7'-0"	U
n7	#4	14'-0"	U
n8	#5	4'-9"	U
n9	#5	6'-8"	U
n10	#4	5'-9"	U
n11	#5	3'-9"	U
F	#4	6'-8"	U
fi	#4	2'-8"	U
U	#4	3'-10"	U
V	#5	9'-9"	U
V1	#4	11'-0"	U
V2	#4	8'-0"	U
V3	#4	9'-9"	U
V4	#4	8'-6"	U
V5	#4	7'-3"	U
V6	#5	11'-0"	U
V7	#4	4'-0"	U
V8	#5	3'-0"	U
W	#5	9'-0"	U
W1	#5	21'-0"	U
W2	#5	25'-6"	U

BILL OF MATERIAL

ITEM	QUANT.
Class X Concrete	C.Y. 61.5
Reinforcement Bars	Lb. 3840
Seal Coat Concrete	C.Y. 5.6
Rock Excavation	C.Y. 11.3
Structure Excavation	C.Y. 165

STA. 238+24.0
 WEST ABUTMENT
 SECTION H-BR-1
 F.A. ROUTE 623
 LA SALLE COUNTY

BRIDGE SHEET 4 OF 5

FILE NAME = ...04007-SN050-2054-005-ExtrngPlans.dgn

ZROKA Engineering, P.C.
 4216 North Hermitage
 Chicago, IL 60613

USER NAME = SAW	DESIGNED - JLA	REVISED -
PLOT SCALE = 0:2.0000 ' / IN.	CHECKED - DAZ	REVISED -
PLOT DATE = 8/15/2012	DRAWN - SAW	REVISED -
	CHECKED - JLA	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

EXISTING BRIDGE PLANS
 FOR INFORMATION ONLY

SHEET NO. 4 OF 7 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
623	(H) BR-1	LA SALLE	32	22
CONTRACT NO. 66A13				
ILLINOIS FED. AID PROJECT				