

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				80% FED, 20% STATE ROADWAY 0004	BOURBONNAIS 100% ROADWAY 0004	BRADLEY 100% ROADWAY 0004	STATE-80% BOURBONNAIS- 10% BRADLEY- 10% TRAFFIC SIGNALS 0021	BOURBONNAIS- 50% BRADLEY- 50% PRE-EMPTION & LIGHTING 0021
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	160	68	51	41		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	85	85				
78200300	PRISMATIC CURB REFLECTOR	EACH	6		6			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	85	85				
* 81028240	UNDERGROUND CONDUIT GALVANIZED STEEL, 4" DIA.	FOOT	344				344	
* 81028320	UNDERGROUND CONDUIT, PVC, 1" DIA	FOOT	52				52	
* 81028350	UNDERGROUND CONDUIT PVC, 2" DIA.	FOOT	52				52	
* 81028360	UNDERGROUND CONDUIT, PVC 2 1/2" DIA.	FOOT	633				633	
* 81028370	UNDERGROUND CONDUIT PVC, 3" DIA.	FOOT	84				84	
* 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	4				4	
* 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1				1	
81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	659					659
82102250	LUMINAIRE, SODIUM VAPOR, HIGH MAST , HORIZONTAL MOUNT, 250 WATT	EACH	4					4
* 85000300	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	LSUM	1				1	

* SPECIAL PROVISION
▲ SPECIALITY ITEM

FILE NAME *	USER NAME * mcfeddanko	DESIGNED -	REVISED -
c:\pwork\pwork\mcfeddanko\0304617\66632\shl\cover.dgn		DRAWN -	REVISED -
PLOT SCALE * 1/80.0115 1/ in.		CHECKED -	REVISED -
PLOT DATE * 9/5/2012		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAP 840 (IL 50) SUMMARY OF QUANTITIES			
SCALE: N.T.S.	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	(140N, TS-3)	KANKAKEE	29	7
CONTRACT NO. 66C32				
ILLINOIS FED. AID PROJECT				

Rev.