

PATCHING SCHEDULE - EASTBOUND LANES								
LOCATION	CLASS A	PATCH	PVMT	SAW	CLASS A	PATCH	PVMT	SAW
	PATCH	REINF.	FABRIC	CUTS	PATCH	REINF.	FABRIC	CUTS
	TYPE II				TYPE II			
STATION	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	SQ YD	SQ YD	FOOT
2944+18	8	8	8	60				
2960+72					8	8	8	60
2962+52					8	8	8	60
2967+10	11	11	11	64				
2967+36					8	8	8	60
2980+34	11	11	11	64				
2990+10					8	8	8	60
2992+90	8	8	8	60	8	8	8	60
3014+88	8	8	8	60	8	8	8	60
3019+10	8	8	8	60				0
3027+02	8	8	8	60				0
3034+41	13	13	13	68				0
TOTALS	75	75	75	496	48	48	48	360

PAVEMENT MARKING SCHEDULE - EBL			
LOCATION	PAINT PAVEMENT MARKING LINE 4"		PAINT PAVEMENT MARKING LINE 6"
	FEET		FEET
	YELLOW	WHITE	WHITE
STATION			
2944+18		6	10
2960+72	6		10
2962+52	6		10
2967+10		8	10
2967+36	6		10
2980+34		8	10
2990+10	6		10
2992+90	6	6	10
3014+88	6	6	10
3019+10		6	10
3027+02		6	10
3034+41		10	10
SUBTOTAL	36	56	
TOTAL		92	120

PATCHING SCHEDULE - WESTBOUND LANES								
LOCATION	CLASS A	PATCH	PVMT	SAW	CLASS A	PATCH	PVMT	SAW
	PATCH	REINF.	FABRIC	CUTS	PATCH	REINF.	FABRIC	CUTS
	TYPE II				TYPE II			
STATION	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	SQ YD	SQ YD	FOOT
2928+84	8	8	8	60	8	8	8	60
2934+12	8	8	8	60	0	0	0	0
2947+56	13	13	13	68	13	13	13	68
2965+24	11	11	11	64	11	11	11	64
2970+00	13	13	13	68				
2987+98	8	8	8	60	0	0	0	0
2990+61	8	8	8	60	8	8	8	60
3018+04	8	8	8	60				
3027+02	8	8	8	60				
TOTALS	46	46	46	560	40	40	40	252

PAVEMENT MARKING SCHEDULE - WBL			
LOCATION	PAINT PAVEMENT MARKING LINE 4"		PAINT PAVEMENT MARKING LINE 6"
	FEET		FEET
	YELLOW	WHITE	WHITE
STATION			
2934+12		6	10
2947+56	10	10	10
2965+24	8	8	10
2970+00		10	10
2987+98		6	10
2990+61	6	6	10
3018+04		6	10
3027+02		6	10
SUBTOTAL	24	58	
TOTAL		82	80