

LO1E L1CE LO1E L1CE LO1E LICE 07CO

SUMMARY OF QUANTITIES

URBAN

ROADWAY FAI 74 / FAI 155

1-155 OVER I-74 (RAMPS G & H)

1-74 OVER ABANDONED RAILROAD DEMOLITION

1-74 OVER JEFFERSON ST

1-74 OVER US 150 (JACKSON ST)

1-74 / I-155

MORTON AVE. OVER I-74


90% FEDERAL 10% STATE

TRAFFIC SIGNALS LIGHTING SIGNING LANDSCAPING INTELLIGENT TRANSPORTATION SYSTEM PINECREST DR PLANS EMERGENCY VEHICLE PRE-EMPTION

100% VILLAGE OF MORTON

CODE	ITEM	UNIT	TOTAL QUANTITY	0003	0008	0044	0010	0010	0040	0014	0021	0021	0021	0031	0021	0014	0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2,011	2011													
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	911	911													
20100500	TREE REMOVAL, ACRES	ACRE	0.50	0.50													
20200100	EARTH EXCAVATION	CU YD	468,371	136,560	331,811												
20400100	BORROW EXCAVATION	CU YD	302,142	71,195	230,947												
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1,544	1,544													
20800150	TRENCH BACKFILL	CU YD	6,982	6,982													
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	258,244	130,135	128,109												
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	196,909	78,342	118,567												
21400100	GRADING AND SHAPING DITCHES	FOOT	2,306	2,306													
* 25000210	SEEDING, CLASS 2A	ACRE	27.75											27.75			
* 25000300	SEEDING, CLASS 3	ACRE	27.25											27.25			
* 25000312	SEEDING, CLASS 4A	ACRE	40.75											40.75			
* 25000322	SEEDING, CLASS 5A	ACRE	68.00											68.00			

\* SPECIALTY ITEM

FILE NAME *	DESIGNED - EJA	REVISED 2/10/23/12		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...General\0468620-shr-500_B1.dgn	DRAWN - TMB	REVISED -				* 50-114R(14B-4,14,14)BIBR	TAZEWELL	2433	8	
USER NAME : jraombilla	CHECKED - JNR	REVISED -				CONTRACT NO. 68620				
PLOT DATE : 7/30/2012	DATE - JULY 20, 2012	REVISED -	SCALE: NTS SHEET NO. 1 OF 34 SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT				