


SUMMARY OF QUANTITIES				L01E		L1CE				L01E		90% FEDERAL L1CE		10% STATE		L01E			L1CE		100% VILLAGE OF MORTON
CODE	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	I-155 OVER	I-74 OVER	I-74 OVER	I-74 OVER	I-74 OVER	I-74 / I-155	MORTON AVE.	TRAFFIC SIGNALS	LIGHTING	SIGNING	LANDSCAPING	INTELLIGENT TRANSPORTATION SYSTEM	PINECREST DR PLANS	EMERGENCY VEHICLE PRE-EMPTION			
				FAI 74 / FAI 155	(RAMPS G & H)	ABANDONED RAILROAD DEMOLITION	JEFFERSON ST	(JACKSON ST)	OVERHEAD SIGN STRUCTURES	OVER I-74	SN 090-0165 (SB) SN 090-0166 (NB)								SN 090-0014 (WB) SN 090-0015 (EB)	SN 090-0167	SN 090-0169
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	267,195	138,732	128,463																
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SO YD	21,088	21,088																	
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SO YD	25,419	25,419																	
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SO YD	267,195	138,732	128,463																
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SO YD	76																		76
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	526	526																	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	2.3		0.5	0.6			0.7												0.5
40600895	CONSTRUCTING TEST STRIP	EACH	3	3																	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	4,222	1,595	800	1,027			800												
40600990	TEMPORARY RAMP	SO YD	6,505	4,694	1,440	172			134												65
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,714	1,714																	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	416	416																	
40603360	HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	708.2		166.2	211.2			242.3												88.5
40702700	FURNISH PROFILOGRAPH	L SUM	1	1																	

* SPECIALTY ITEM

FILE NAME : ...General\0468620\shc-500_03.dgn	DESIGNED - EJA	REVISED 2 10/23/2012	 <p>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p>	SUMMARY OF QUANTITIES			F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME : pambillo	DRAWN - TMB	REVISED -		SCALE: NTS	SHEET NO. 3 OF 34 SHEETS	STA. TO STA.	90-114R(14)B-4,14,14HVBIBR	TAZEWELL	2433	10	
PLOT DATE : 7/30/2012	CHECKED - JNR	REVISED -					CONTRACT NO. 68620		ILLINOIS FED. AID PROJECT		
	DATE - JULY 20, 2012	REVISED -									