


LOCATION			PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	MEDIAN REMOVAL	PAVED DITCH REMOVAL	PAVED SHOULDER REMOVAL	CONCRETE HEADWALL REMOVAL	PIPE CULVERT REMOVAL	STORM SEWER REMOVAL 12"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 18"	STORM SEWER REMOVAL 24"
ROAD	STATION FROM	STATION TO	SO YD	SO YD	FOOT	SO FT	FOOT	SO YD	EACH	FOOT	FOOT	FOOT	FOOT	FOOT
I-474	-	456+00.00	0	0	0	0	0	0	0	0	0	0	0	0
I-74	456+00.00	471+00.00	2573	0	0	0	54	3606	0	0	0	0	0	95
I-74	471+00.00	486+00.00	11103	0	0	0	0	7289	0	0	0	0	0	95
I-74	486+00.00	501+00.00	11986	0	0	0	0	6905	0	0	0	0	0	171
I-74	501+00.00	516+00.00	12761	0	0	0	0	6590	2	175	0	0	0	0
I-74	516+00.00	531+00.00	15544	0	0	0	0	9563	3	612	0	0	0	173
RAMP G/H	118+50.00	101+47.00	4968	0	0	0	0	3101	5	328	0	0	0	229
I-74	531+00.00	546+00.00	12310	0	0	0	100	7713	5	0	172	156	0	168
I-74	546+00.00	561+00.00	12700	0	226	3862	0	5353	0	0	0	174	60	0
I-74	561+00.00	576+00.00	8824	108	0	826	0	4888	6	225	0	402	0	0
I-74	576+00.00	591+00.00	12056	362	221	0	955	6987	4	384	0	179	0	20
I-74	591+00.00	606+00.00	7668	0	731	5993	314	4319	0	0	0	0	0	72
I-74	606+00.00	621+00.00	2692	0	0	0	0	2174	0	0	0	0	0	0
I-74	621+00.00	636+00.00	0	0	0	0	0	0	0	0	0	0	0	0
I-74	636+00.00	640+00.00	0	0	0	0	0	0	0	0	0	0	0	0
I-155	1+50.00	9+00.00	2663	0	0	0	0	1824	4	838	0	28	0	94
I-155	9+00.00	23+00.00	10446	0	0	0	0	6146	0	241	0	0	0	0
I-155	23+00.00	37+50.00	7403	0	0	0	0	4633	0	0	0	0	0	0
I-155	37+50.00	51+00.00	0	0	0	0	0	1070	0	0	0	0	0	0
I-155	51+00.00	66+00.00	0	0	0	0	0	0	0	0	0	0	0	0
Morton Ave.	16+00.00	28+25.00	1178	0	1183	2060	0	58	0	0	47	0	0	0
Morton Ave.	28+25.00	36+50.00	11326	0	2170	10428	0	3872	0	195	292	0	0	0
Morton Ave.	36+50.00	44+75.00	5847	0	1874	9730	24	1658	0	0	0	0	0	0
Morton Ave.	44+75.00	58+00.00	3397	0	1046	953	0	253	0	144	0	188	0	0
TOTAL			157,445	470	7,451	33,852	1,447	88,002	29	3,142	511	1,127	60	1,117

			STORM SEWER REMOVAL 30"	STORM SEWER REMOVAL 36"	STORM SEWER REMOVAL 48"	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	GUARDRAIL REMOVAL	CABLE ROAD GUARD REMOVAL	REMOVE EXISTING RIPRAP	REMOVING AND REPLACING EXPANSION JOINT
ROAD	STATION FROM	STATION TO	FOOT	FOOT	FOOT	EACH	EACH	EACH	FOOT	FOOT	SO YD	FOOT
I-474	-	456+00.00	0	0	0	0	0	0	0	0	0	0
I-74	456+00.00	471+00.00	0	0	0	0	0	0	516	1098	0	0
I-74	471+00.00	486+00.00	0	0	0	0	0	1	885	1417	0	0
I-74	486+00.00	501+00.00	0	0	0	0	0	1	1598	1097	0	0
I-74	501+00.00	516+00.00	0	0	0	0	1	0	1368	1153	0	0
I-74	516+00.00	531+00.00	0	0	0	0	0	2	819	1498	0	0
RAMP G/H	118+50.00	101+47.00	0	0	0	0	0	0	0	0	218	0
I-74	531+00.00	546+00.00	101	0	50	0	1	6	5481	797	0	0
I-74	546+00.00	561+00.00	0	0	0	0	0	3	4852	584	8	0
I-74	561+00.00	576+00.00	0	0	0	0	0	5	3700	802	0	0
I-74	576+00.00	591+00.00	0	168	150	2	1	3	223	1393	40	0
I-74	591+00.00	606+00.00	0	22	0	0	1	0	63	0	0	0
I-74	606+00.00	621+00.00	0	8	0	0	0	1	0	0	0	0
I-74	621+00.00	636+00.00	0	0	0	0	0	0	0	0	0	0
I-74	636+00.00	640+00.00	0	0	0	0	0	0	0	0	0	0
I-155	1+50.00	9+00.00	0	0	0	0	0	3	854	0	0	0
I-155	9+00.00	23+00.00	0	0	0	0	0	0	0	0	182	0
I-155	23+00.00	37+50.00	0	0	0	0	0	0	0	0	717	82
I-155	37+50.00	51+00.00	0	0	0	0	1	0	0	0	0	0
I-155	51+00.00	66+00.00	0	0	0	0	1	0	0	0	0	0
Morton Ave.	16+00.00	28+25.00	0	0	0	0	1	0	0	0	0	0
Morton Ave.	28+25.00	36+50.00	0	91	0	2	2	1	354	0	43	0
Morton Ave.	36+50.00	44+75.00	0	8	0	0	0	0	63	0	0	0
Morton Ave.	44+75.00	58+00.00	0	0	0	1	0	4	0	0	0	0
TOTAL			101	297	200	5	9	30	20,776	9,839	1,208	82

NOTE

- SEE SIGN SCHEDULE SHEETS FOR EACH STAGE FOR REMOVAL SCHEDULES ASSOCIATED WITH SIGNS AND SIGN STRUCTURES.
- SEE SCHEDULE OF QUANTITIES FOR EACH STAGE FOR PAVEMENT MARKING REMOVAL SCHEDULE

FILE NAME : 0458628-int-schedule-rn.dgn	DESIGNED - HTL	REVISED - 10/23/2012 HTL		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MAINTENANCE OF TRAFFIC TEMPORARY PAVEMENT DETAILS	F.A.I. RTE. : 90-114R-114HB-4,14,14HVBIBR	SECTION : TAZEWELL	COUNTY : TAZEWELL	TOTAL SHEETS : 2433	SHEET NO. : 77
USER NAME : TERRA	CHECKED - DA/LVA	REVISED -				CONTRACT NO. : 68620				
PLOT DATE : 7/23/2012	DATE : 7/20/2012	REVISED -				ILLINOIS FED. AID PROJECT				