

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURE
				F. A. P. 574 80% FEDERAL 20% STATE	S. N. 029-0072 80% FEDERAL 20% STATE
				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
				0004	0011
44000100	PAVEMENT REMOVAL	SO YD	157	157	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	263	263	
44004250	PAVED SHOULDER REMOVAL	SO YD	176	176	
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SO YD	172	172	
48203003	HOT-MIX ASPHALT SHOULDERS, 1 1/2"	SO YD	198	198	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	198	198	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	168	168	
50200100	STRUCTURE EXCAVATION	CU YD	46		46
50200300	COFFERDAM EXCAVATION	CU YD	10		10
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1		1
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	120.6		120.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	252.8		252.8