

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURE
				F. A. P. 574 80% FEDERAL 20% STATE	S. N. 029-0072 80% FEDERAL 20% STATE
				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
				0004	0011
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1038	1038	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	700	700	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	587.5	587.5	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2964	2964	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SO FT	800	800	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10	
Z0001002	GUARDRAIL AGGREGATE EROSION CONTROL	TON	205	205	
Z0001900	ASBESTO BEARING PAD REMOVAL	EACH	24		24
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0026407	TEMPORARY SHEET PILING	SO FT	380		380
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4	
* Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2	