

EARTHWORK SCHEDULE				
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
STA. 398+50 TO STA. 401+88.20	176	132	371	-239
STA. 402+64.20 TO STA. 405+91	320	240	126	114
TOTAL	496	372	497	-125

GUARDRAIL SCHEDULE				
LOCATION	SPBGR TYPE A, 6' POSTS	TRAFFIC BARRIER TERMINAL TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 1 (SPECIAL TANGENT)	TERMINAL MARKER - DIRECT APPLIED
	FOOT	EACH	EACH	EACH
STA. 399+93.01 LT.				1
STA. 399+93.01 TO STA. 400+43.01 LT.			1	
STA. 400+43.01 TO STA. 401+30.51 LT.	87.5			
STA. 401+30.51 TO STA. 401+73.66 LT.		1		
STA. 402+78.74 TO STA. 403+21.89 LT.		1		
STA. 403+21.89 TO STA. 405+09.39 LT.	187.5			
STA. 405+09.39 TO STA. 405+59.39 LT.			1	
STA. 405+59.39 LT.				1
STA. 398+93.01 RT.				1
STA. 398+93.01 TO STA. 399+43.01 RT.			1	
STA. 399+43.01 TO STA. 401+30.51 RT.	187.5			
STA. 401+30.51 TO STA. 401+73.66 RT.		1		
STA. 402+78.74 TO STA. 403+21.89 RT.		1		
STA. 403+21.89 TO STA. 403+71.89 RT.			1	
STA. 403+71.89 RT.				1
TOTAL	462.5	4	4	4

CHANNEL EXCAVATION SCHEDULE	
LOCATION	CHANNEL EXCAVATION
	CU. YD.
STA. 401+88.20, 70' LT. TO STA. 402+64.2, 75' RT.	533
TOTAL	533

BRIDGE APPR. PVMT. CONN. (FLEX) SCHEDULE	
LOCATION	BRIDGE APPR PVMT CONN
	SO. YD.
STA. 401+52.70 TO STA. 401+58.70	21.5
STA. 402+93.70 TO STA. 405+99.70	21.5
TOTAL	43

PAVED SHOULDER REMOVAL SCHEDULE	
LOCATION	PAVED SHOULDER REMOVAL
	SO. YD.
STA. 398+60 TO STA. 400+50 RT.	85
STA. 403+75 TO STA. 405+80 RT.	91
TOTAL	176

TREE REMOVAL SCHEDULE	
LOCATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)
	UNIT
STA. 401+47, 33' RT.	2 x 7 = 14
STA. 401+56, 44' RT.	2 x 7 = 14
STA. 401+94, 44' RT.	4 x 8 = 32
TOTAL	60

PIPE CULVERT REMOVAL SCHEDULE	
LOCATION	PIPE CULVERT REMOVAL
	FOOT
STA. 402+43, 22' RT. TO STA. 404+11, 24' RT.	168
TOTAL	168

AGGREGATE SURFACE COURSE, TYPE B SCHEDULE	
LOCATION	AGGREGATE SURFACE COURSE, TYPE B
	TON
P.E. STA. 404+23 RT.	132
TOTAL	132

PAVEMENT REMOVAL SCHEDULE	
LOCATION	PAVEMENT REMOVAL
	SO. YD.
STA. 401+80.2 TO STA. 402+06.5	76
STA. 402+44.5 TO STA. 402+72.2	81
TOTAL	157

GUARDRAIL REMOVAL SCHEDULE	
LOCATION	GUARDRAIL REMOVAL
	FOOT
STA. 401+10 TO STA. 401+87 LT.	77
STA. 402+64 TO STA. 403+41 LT.	77
STA. 401+10 TO STA. 401+87 RT.	77
STA. 402+64 TO STA. 402+91 RT.	27
TOTAL	258

AGGREGATE FOR TEMPORARY ACCESS SCHEDULE	
LOCATION	AGGREGATE TEMPORARY ACCESS
	TON
P. E. STA. 403+87 RT.	10
TOTAL	10

TEMPORARY RAMP SCHEDULE	
LOCATION	TEMPORARY RAMP
	SO. YD.
STA. 398+50 TO STA. 398+55	14.5
STA. 399+52.5 TO STA. 399+60	22
STA. 404+20 TO STA. 404+27.5	22
STA. 405+86 TO STA. 405+91	14.5
TOTAL	73

SUB-BASE GRANULAR MATERIAL, TYPE A SCHEDULE	
LOCATION	QUANTITY
	TON
STA. 401+65.7 TO STA. 401+82	58
STA. 402+70.4 TO STA. 402+86.7	50
TOTAL	108

MATERIAL TRANSFER DEVICE SCHEDULE	
LOCATION	QUANTITY
	TON
STA. 398+50 TO STA. 399+60	27
STA. 399+60 TO STA. 401+52.7	117
STA. 402+99.7 TO STA. 404+20	73
STA. 404+20 TO STA. 405+91	42
TOTAL	259

RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE		
LOCATION	RRPM	RRPM REMOVAL
	EACH	EACH
STA. 398+50 TO STA. 405+91	10	
STA. 398+50 TO STA. 401+80.2		5
STA. 402+72.20 TO STA. 405+91		5
TOTAL	10	10

SEEDING SCHEDULE					
LOCATION	SEEDING CLASS A2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2
	ACRE	POUND	POUND	POUND	ACRE
STA. 398+50 TO STA. 405+91 LT.	0.3	27	27	27	0.3
STA. 398+50 TO STA. 405+91 RT.	0.4	36	36	36	0.4
TOTAL	0.7	63	63	63	0.7

USER NAME = *USER*	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = *SCALE*	CHECKED -	REVISED -
PLOT DATE = *DATE*	DATE -	REVISED -



Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL
62703 Phone: (217)544-8033 IL Design Firm
No. 184-001907

QUANTITY SCHEDULES		
SCALE: NONE	SHEET NO. 1 OF 2 SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
574	12BR-1	FULTON	62	13
CONTRACT NO. 68732				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				