

FLEXIBLE DELINEATORS			
LOCATION	EACH	WHITE	YELLOW
ATLANTA INTERCHANGE (I-55)			
STA 402+00 TO STA 577+25	130	130	0
RAMP A	40	25	15
RAMP B	26	20	6
RAMP C	38	24	14
RAMP D	24	19	5
SUBTOTAL		258	40
HARTSBURG INTERCHANGE (I-155)			
STA 270+00 TO STA 370+00	88	88	0
RAMP A	23	17	6
RAMP B	27	21	6
RAMP C	23	17	6
RAMP D	27	21	6
SUBTOTAL		188	24
WILLIAMSVILLE INTERCHANGE (I-55)			
STA 263+00 TO STA 407+00	96	96	0
RAMP A	35	26	9
RAMP B	37	26	11
RAMP C	31	21	10
RAMP D	56	37	19
SUBTOTAL		255	49
TOTAL		701	113

DELINEATOR REMOVAL	
LOCATION	EACH
ATLANTA INTERCHANGE (I-55)	
STA 402+00 TO STA 577+25	36
RAMP A	13
RAMP B	9
RAMP C	12
RAMP D	8
SUBTOTAL	
HARTSBURG INTERCHANGE (I-155)	
STA 270+00 TO STA 370+00	9
RAMP A	11
RAMP B	10
RAMP C	11
RAMP D	10
SUBTOTAL	
WILLIAMSVILLE INTERCHANGE (I-55)	
STA 263+00 TO STA 407+00	11
RAMP A	13
RAMP B	15
RAMP C	8
RAMP D	16
SUBTOTAL	
TOTAL	
192	