

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	L25E ACF	LS3E ACHSIP
				ROADWAY F. A. P. 67 80% FEDERAL 20% STATE	ROADWAY F. A. P. 67 90% FEDERAL 10% STATE
				CONSTRUCTION TYPE CODE 0005	CONSTRUCTION TYPE CODE 0021
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.8	7.8	
40600300	AGGREGATE (PRIME COAT)	TON	41.2	41.2	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	390	390	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	456	456	
40600990	TEMPORARY RAMP	SO YD	71	71	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	754	754	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	180	180	
44000100	PAVEMENT REMOVAL	SO YD	131		131
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	107		107
44004250	PAVED SHOULDER REMOVAL	SO YD	4194		4194
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	100	100	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3789		3789
48101200	AGGREGATE SHOULDERS, TYPE B	TON	416	416	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	2299		2,299