

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	100% State
			0014
			TOTAL QTY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	117
35650400	BASE COURSE WIDENING, 9"	SQ YD	467
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	356
40600990	TEMPORARY RAMP	SQ YD	85
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	104
48101200	AGGREGATE SHOULDERS, TYPE B	TON	24
50102400	CONCRETE REMOVAL	CU YD	20
50300255	CONCRETE SUPERSTRUCTURE	CU YD	22
50300260	BRIDGE DECK GROOVING	SQ YD	2380
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3160
50800515	BAR SPLICERS	EACH	59
52000110	PREFORMED JOINT STRIP SEAL	FOOT	150
63301215	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL, TYPE B	FOOT	25
63301235	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	25

QUANTITIES
FAP 608 (IL 111)
SECTION (126)I-1
MACOUPIN COUNTY