

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004 90% FEDERAL 10% STATE		
60107700	PIPE UNDERDRAINS 6"	FOOT	118572	118572		
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	5796	5796		
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	2025	2025		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	8	8		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	12	12		
63200310	GUARDRAIL REMOVAL	FOOT	4316	4316		
63400105	GUARD POSTS	EACH	196	196		
63500105	DELINEATORS	EACH	276	276		
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	159560	159560		
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	8	8		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		
67000600	ENGINEER'S FIELD LAB	CAL MO	9	9		
67100100	MOBILIZATION	L SUM	1	1		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004 90% FEDERAL 10% STATE		
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	8	8		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20		
* 70300100	SHORT TERM PAVEMENT MARKING	FOOT	30262	30262		
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	153336	153336		
* 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	19167	19167		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	103732	103732		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	7600	7600		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	7600	7600		
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INTERNAL-LINE 6"	FOOT	19,070	19,070		
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	153336	153336		
* 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	97	97		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1907	1907		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12	12		

* SPECIALTY ITEM



FILE NAME =	USER NAME = teasleyk	DESIGNED -	REVISION 10/29/12	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\teasleyk\08148656\07	4416-sh-t-sqa.dgn	DRAWN -	REVISION -					70	(18-47,48,49)R	CUMBERLAND	30	4	
	PLOT SCALE = 100,0000 1/4 in.	CHECKED -	REVISION -										
	PLOT DATE = 8/17/2012	DATE -	REVISION -										
								SCALE: NA		SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT	
										CONTRACT NO. 74416			

2012 05 01

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004 90% FEDERAL 10% STATE		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	1467	1467		
X5012650	CONCRETE HEADWALL REMOVAL SPECIAL	EACH	250	250		
X6350120	DELINEATOR REMOVAL	EACH	276	276		
X7010805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	L SUM	1	1		
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14	14		
*X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	153336	153336		
*X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	97	97		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	8	8		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	8	8		
Z0034105	MATERIAL TRANSFER DEVICE	TON	49967	49967		
Z0055605	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	SO YD	130960	130960		
Z0056220	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED	EACH	8	8		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004 90% FEDERAL 10% STATE		
+ Z0076600	TRAINEES	HOUR	1500	1500		
+ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1500	1500		

+ Z0076604 TRAINEES TRAINING PROGRAM GRADUATE



* SPECIALTY ITEM + 0042