

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004 90% FEDERAL 10% STATE		
X0327487	TRIAXIAL GEOGRID REINFORCEMENT, TYPE I	SO YD	15467	15467		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2362	2362		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1758	1758		
20100500	TREE REMOVAL, ACRES	ACRE	0.75	0.75		
28100703	STONE DUMPED RIPRAP, CLASS A2	SO YD	6898	6898		
35501303	HOT-MIX ASPHALT BASE COURSE, 4 3/4"	SO YD	12800	12800		
35501335	HOT-MIX ASPHALT BASE COURSE, 12 3/4"	SO YD	2667	2667		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	45484	45484		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	10511	10511		
40600990	TEMPORARY RAMP	SO YD	474	474		
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	62342	62342		
40603100	HOT-MIX ASPHALT BINDER COURSE, IL-19.0L, N30	TON	16132	16132		
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	26444	26444		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004 90% FEDERAL 10% STATE		
40603244	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N105	TON	23002	23002		
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	3629	3629		
44000100	PAVEMENT REMOVAL	SO YD	15467	15467		
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SO YD	67436	67436		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	10311	10311		
44000175	HOT-MIX ASPHALT SURFACE REMOVAL, 6 1/2"	SO YD	140293	140293		
44004250	PAVED SHOULDER REMOVAL	SO YD	70600	70600		
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	19724	19724		
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SO YD	38060	38060		
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SO YD	32540	32540		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	17612	17612		
50800105	REINFORCEMENT BARS	POUND	8900	8900		
60100078	SHOULDER REMOVAL AND REPLACEMENT 12 1/2"	FOOT	65962	65962		

FILE NAME :	USER NAME : teasleyck	DESIGNED -	REVISED -
c:\pwwork\pwwork\teasleyck\d0148656\07	4416\shl-sea.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 1/16"	CHECKED -	REVISED -
	PLOT DATE = 8/17/2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(18-47,48,49)R	CUMBERLAND	30	3
CONTRACT NO. 74416				
ILLINOIS FED. AID PROJECT				