

PAVEMENT MARKING SCHEDULE

STATION TO	STATION	LENGTH (FEET)	SHORT-TERM PAVEMENT MARKING (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	TEMPORARY PAVEMENT MARKING - LINE 4" (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 6" (FOOT)	MODIFIED URETHANE PAVEMENT MARKING - LINE 4" (FOOT)	MODIFIED URETHANE PAVEMENT MARKING - LINE 6" (FOOT)	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6" (FOOT)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) (EACH)	GROOVING FOR RECESSED PAVEMENT MARKING 5" (FOOT)	GROOVING FOR RECESSED PAVEMENT MARKING 7" (FOOT)	DELINEATOR REMOVAL (EACH)	DELINEATORS (EACH)
EASTBOUND															
292+20	TO 344+62	5242	1887	10044	10484	1311	10484		1311	131		10484		15	15
344+62	TO 352+62	800	288	2181	1600	200	1600		200	20		1600		2	2
352+62	TO 430+30	7768	2796	12097	15536	1942	15536		1942	194		15536		33	33
430+30	TO 438+30	800	288	2181	1600	200	1600		200	20		1600		3	3
438+30	TO 486+23	4793	1726	4303	9586	1198	9586		1198	120		9586		24	24
486+23	TO 488+17	194		259	388	49	388	49			6	388	49	1	1
488+17	TO 525+68	3751	1351	6500	7502	938	7502		938	94		7502		19	19
525+68	TO 533+68	800	288	2181	1600	200	1600		200	20		1600		5	5
533+68	TO 617+42	8374	3015	12941	16748	2094	16748		2094	210		16748		21	21
617+42	TO 625+42	800	288	2181	1600	200	1600		200	20		1600		2	2
625+42	TO 675+54	5012	1804	6983	10024	1253	10024		1253	125		10024		13	13
EASTBOUND TOTALS			13731	61851	76668	9584	76668	49	9535	954	6	76668	49	138	138
WESTBOUND															
292+20	TO 346+38	5418	2926	325	10836	1355	10836		1355	136		10836.0		16	16
346+38	TO 351+38	500	180	697	1000	125	1000		125	31		1000.0		1	1
351+38	TO 432+05	8067	4356	1757	16134	2017	16134		2017	183		16134.0		34	34
432+05	TO 437+05	500	180	697	1000	125	1000		125	31		1000.0		1	1
437+05	TO 457+80	2075	1121	1398	4150	519	4150		519	33		4150.0		12	12
457+80	TO 486+23	2843	1023	3961	5686	711	5686		711	71		5686.0		13	13
486+23	TO 488+17	194		259	388	49	388	49			6	388	49	1	1
488+17	TO 525+94	3777	1360	5263	7554	944	7554		944	94		7554.0		19	19
525+94	TO 533+94	800	288	2181	1600	200	1600		200	20		1600.0		5	5
533+94	TO 617+42	8348	3005	12905	16696	2087	16696		2087	209		16696.0		21	21
617+42	TO 625+42	800	288	2181	1600	200	1600		200	20		1600.0		2	2
625+42	TO 675+54	5012	1804	10257	10024	1253	10024		1253	125		10024.0		13	13
WESTBOUND TOTALS			16531	41880	76668	9584	76668	49	9535	953	6	76668	49	138	138
TOTALS			30262	103732	153336	19167	153336	97	19070	1907	12	153336	97	276	276

