



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 26, 2012

SUBJECT: FAI Route 70(I-70)
Project ACIM-070-4(142)120
Section (18-47-VB)K, (18-47B, 18-47HB)BR
Cumberland County
Contract No. 74466
Item No. 39, November 9, 2012 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised sheet 3 of the Plans.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Revised pages 60 and 61 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli,
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with "P.E." written in smaller letters at the end.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Roger Driskell, Region 4, District 7; Mike Renner; D. Carl Puzey;
Estimates

dr

JACKING EXISTING SUPERSTRUCTURE	35
STRUCTURAL REPAIR OF CONCRETE	37
TEMPORARY CONSTRUCTION ACCESS	46
LINEAR DELINEATION PANELS	46
STRUCTURAL STEEL REMOVAL.....	48
JACKING AND CRIBBING.....	48
DECK SLAB REPAIR.....	49
HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	55
PARTIAL DEPTH PAVEMENT PATCHING	55
STRUCTURAL STEEL REPAIR	57
WEEP HOLE DRAINS FOR ABUTMENTS, WINGWALLS, RETAINING WALLS AND CULVERTS	58
AGREEMENT TO PLAN QUANTITY (BDE).....	58
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE).....	58
COARSE AGGREGATE IN BRIDGE APPROACH SLABS/FOOTINGS (BDE).....	60
CONCRETE MIX DESIGN – DEPARTMENT PROVIDED (BDE)	61
CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE)	61
CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE).....	62
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	64
ERRATA FOR THE 2012 STANDARD SPECIFICATIONS (BDE).....	73
FLAGGER AT SIDE ROADS AND ENTRANCES (BDE)	74
FRICTION AGGREGATE (BDE)	75
GRANULAR MATERIALS (BDE).....	78
HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE)	78
METAL HARDWARE CAST INTO CONCRETE (BDE).....	79
PAVEMENT MARKING REMOVAL (BDE)	80
PAVEMENT PATCHING (BDE).....	80
PAYMENTS TO SUBCONTRACTORS (BDE)	81
PLANTING WOODY PLANTS (BDE)	82
PORTLAND CEMENT CONCRETE (BDE)	83
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE)	119
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	129
REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE)	133
SELF-CONSOLIDATING CONCRETE FOR PRECAST AND PRECAST PRESTRESSED PRODUCTS (BDE).....	134
SHOULDER RUMBLE STRIPS (BDE)	136

Basis of Payment. This work will not be paid for separately but shall be considered as included in the cost of the various traffic control items included in the contract.

COARSE AGGREGATE IN BRIDGE APPROACH SLABS/FOOTINGS (BDE)

Effective: April 1, 2012

Revise the third paragraph of Article 1004.01(b) of the Standard Specifications to read:

“Aggregates used in Class BS concrete (except when poured on subgrade), Class PS concrete, and Class PC concrete (superstructure products only) shall contain no more than two percent by weight (mass) of deleterious materials. Deleterious materials shall include substances whose disintegration is accompanied by an increase in volume which may cause spalling of the concrete.”

Revise the first sentence of the first paragraph of Article 1004.02(f) of the Standard Specifications to read:

“(f) Freeze-Thaw Rating. When coarse aggregate is used to produce portland cement concrete for base course, base course widening, pavement, driveway pavement, sidewalk, shoulders, curb, gutter, combination curb and gutter, median, paved ditch, concrete superstructures on subgrade such as bridge approach slabs, concrete structures on subgrade such as bridge approach footings, or their repair using concrete, the gradation permitted will be determined from the results of the Department’s Freeze-Thaw Test (Illinois Modified AASHTO T 161).”

Revised 10/26/2012

CONCRETE MIX DESIGN – DEPARTMENT PROVIDED (BDE)

Effective: January 1, 2012

For the “Portland Cement Concrete (BDE)” special provision included in this project, specifically Article 1020.05(a), the Contractor has the option to request the Engineer determine mix design material proportions for Class PV, PP, RR, BS, DS, SC, and SI concrete. A single mix design for each class of concrete will be provided. Acceptance by the Contractor to use the mix design developed by the Engineer shall not relieve the Contractor from meeting specification requirements.

CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE)

Effective: April 1, 2009

Revised: January 2, 2012

Diesel Vehicle Emissions Control. The reduction of construction air emissions shall be accomplished by using cleaner burning diesel fuel. The term “equipment” refers to any and all diesel fuel powered devices rated at 50 hp and above, to be used on the project site in excess of seven calendar days over the course of the construction period on the project site (including any “rental” equipment).

All equipment on the jobsite, with engine ratings of 50 hp and above, shall be required to: use Ultra Low Sulfur Diesel fuel (ULSD) exclusively (15 ppm sulfur content or less).

Diesel powered equipment in non-compliance will not be allowed to be used on the project site, and is also subject to a notice of non-compliance as outlined below.

The Contractor shall certify that only ULSD will be used in all jobsite equipment. The certification shall be presented to the Department prior to the commencement of the work.

Revised 10/26/2012