

90% FED
10% STATE

90% FED
10% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		SN 018-0045 SN 018-0046 0004	SN 018-0047 SN 018-0048 0014	SN 018-0049 SN 018-0050 0014
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1018		534	484
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	532	78	129	325
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	1499	282	640	577
40702006	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 16 1/4"	SO YD	1152	1152		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	208		106.7	101.3
44000100	PAVEMENT REMOVAL	SO YD	208		106.7	101.3
44004250	PAVED SHOULDER REMOVAL	SO YD	13430	12275	732	423
44200616	CLASS A PATCHES, TYPE I, 14 INCH	SO YD	8	8		
44200620	CLASS A PATCHES, TYPE II, 14 INCH	SO YD	67	67		
44200624	CLASS A PATCHES, TYPE III, 14 INCH	SO YD	37	37		
44200628	CLASS A PATCHES, TYPE IV, 14 INCH	SO YD	227	227		
44213000	PATCHING REINFORCEMENT	SO YD	338	338		

SUMMARY OF QUANTITIES				TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	SN 018-0045 SN 018-0046 0004		SN 018-0047 SN 018-0048 0014	SN 018-0049 SN 018-0050 0014	
44213200	SAW CUTS	FOOT	1164	1164			
44213204	TIE BARS 3/4"	EACH	146	146			
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	698	96	312	290	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	98		53	45	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	528	528			
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1			
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1			
50102400	CONCRETE REMOVAL	CU YD	127.8		68.5	59.3	
50104650	SLOPE WALL REMOVAL	SO YD	2297	2215	55	27	
50104701	REMOVAL OF EXISTING CONCRETE DECK NO. 1	EACH	1		1		
50104702	REMOVAL OF EXISTING CONCRETE DECK NO. 2	EACH	1		1		
50104703	REMOVAL OF EXISTING CONCRETE DECK NO. 3	EACH	1			1	
50104704	REMOVAL OF EXISTING CONCRETE DECK NO. 4	EACH	1			1	
50157300	PROTECTIVE SHIELD	SO YD	484		484		

FILE NAME :	USER NAME : stoffenmk	DESIGNED -	REVISED -
c:\p\work\perdst\stoeffenmk\d2106453\d74466-shr-acc.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: NA	SHEET NO. 2 OF 6 SHEETS	STA.	TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70		CUMBERLAND	147	5
CONTRACT NO. 74466				
ILLINOIS FED. AID PROJECT				

(18-47-VB1K,18-47B,18-47HB)BR