

90% FED
10% STATE

90% FED
10% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		SN 018-0045 SN 018-0046 0004	SN 018-0047 SN 018-0048 0014	SN 018-0049 SN 018-0050 0014
X6650202	WOVEN WIRE FENCE REMOVAL	FOOT	850	850		
* X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	6	2	2	2
* X7270008	BREAKAWAY SIGN SUPPORT COUPLER	EACH	36	36		
* X7810400	TEMPORARY RAISED PAVEMENT MARKER	EACH	688	688		
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	66		42	24
Z0001904	STRUCTURAL STEEL REMOVAL	L SUM	1			1
Z0001905	STRUCTURAL STEEL REPAIR	POUND	1330			1330
Z0004552	APPROACH SLAB REMOVAL	SO YD	1546	533	533	480
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SO YD	693	693		
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	462		6	456
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	7			7
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	65	3	21	41

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		SN 018-0045 SN 018-0046 0004	SN 018-0047 SN 018-0048 0014	SN 018-0049 SN 018-0050 0014
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	130	6	42	82
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	257	11	84	162
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	14		2	12
Z0024478	FLEXIBLE DELINEATORS	EACH	36	36		
Z0031200	JACKING AND CRIBBING	EACH	24			24
Z0032300	JACKING EXISTING SUPERSTRUCTURE	L SUM	1			1
Z0034390	MODULAR EXPANSION JOINT 6"	FOOT	76			76
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	483		268	215
Z0065730	SLOPE WALL SLURRY PUMPING	CU YD	57		57	
Z0076600	TRAINEES	HOUR	1000	333	334	333
Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1000	333	334	333

* SPECIALTY ITEM

0042

FILE NAME =	USER NAME = staffernk	DESIGNED -	REVISED -
c:\pwork\pwork\staffernk\d0186453\d7	74460-shr-soq.dgn	DRAWN -	REVISED -
	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -
	PLOT DATE = 8/20/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 6 OF 6 SHEETS STA. TO STA.

(18-47-VB)K(18-47B,18-47HB)BR

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70		CUMBERLAND	147	9
CONTRACT NO. 74466			ILLINOIS FED. AID PROJECT	