

PAVEMENT MARKING SCHEDULE

LOCATION STA TO STA	PERFORMED PAVT. MARKING-TYPE B-INLAID						GROOVING FOR RECESSED PAVT. MARKING							
	LETTERS & SYMBOLS SQ FT	-LINE 4"			-LINE 12" FOOT	- LINE 24" FOOT	LETTERS & SYMBOLS SQ FT	-LINE 5"		-LINE 13" FOOT	- LINE 25" FOOT			
		WHITE		YELLOW				SOLID	SKIP DASH			SOLID	FOOT	FOOT
		SOLID	SKIP DASH	SOLID										
BENTLEY ST.														
RT STA 9+40.76											29.0			
LT STA 10+58.93											33.0			
VICKSBURG ST.														
RT STA 9+27.81											18.0			
LT STA 10+55.44											29.0			
HIGHLAND ST.														
RT STA 9+34.38											23.0			
JOHNSON ST.														
RT STA 9+02.48											20.8			
RT STA 9+28.06											15.6			
RT STA 9+46.00											19.0			
LT STA 10+58.43											14.0			
LT STA 10+70.14											15.6			
LT STA 10+95.78											20.8			
RUSSEL ST.														
STA 8+00.00 TO STA 9+19.93											120.0			
RT STA 8+07.82											20.8			
RT STA 8+61.60											20.8			
STA 8+65.00											15.6			
RT STA 8+87.28											15.6			
LT STA 9+07.28 TO STA 10+57.45											306.0			
RT STA 9+13.56											18.0			
RT STA 9+20.06											24.0			
LT STA 10+70.02											44.0			
STA 10+70.02 TO STA 11+80.98											333.0			
RT STA 11+02.34											21.7			
STA 11+09.25											31.2			
RT STA 11+59.50											15.6			
STA 11+66.16											41.6			
SHEET 3 SUB TOTALS	255.7	759.0	0.0	462.0	0.0	251.0	255.7	1,221.0	0.0	0.0	251.0			
SHEET 3 TOTALS	255.7		1,221.0		0.0	251.0	255.7	1,221.0	0.0	0.0	251.0			
SHEET 2 TOTALS	249.7		4,036.0		167.7	84.0	119.5	2,468.0	167.7	84.0				
SHEET 1 TOTALS	245.4		5,468.0		141.3	78.0	94.6	2,672.0	141.3	78.0				
PROJECT TOTAL	751		10,725		309	413	470	6,361	309	413				

NOTES: 1) SEE SHEET 148 FOR DETAIL OF STRAIGHT ARROW AND BIKE SYMBOL.
 2) ALL LEFT AND RIGHT ARROWS ARE LARGE SIZE, "ONLY" LETTERS ARE TO BE 8' IN HEIGHT.

FILE NAME :	USER NAME : #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE - PAVEMENT MARKING 3 OF 3	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\pwork\pawdot\kellgk\d0184451\78203	ahrsched.dgn	DRAWN -	REVISED -			331	(IX-1)R-5,RS-3,N-5,TS-4	WILLIAMSON	288	49
PLOT SCALE = 1/80,000' / 1" =	CHECKED -	REVISED -	REVISED -							
PLOT DATE = 5/11/2012	DATE -	REVISED -	REVISED -							
										CONTRACT NO. 78203
										(ILLINOIS) FED. AID PROJECT