

RESURFACING SCHEDULE (CONT)

LOCATION STATION TO STATION	LENGTH	PAVED SHLD REM 8"	HMA SURF REM, 1"	HMA SURF REM, 1 3/4"	HMA SURF REM, 2"	HMA SURF REM, 3"	RUBBLIZE PCC PAVEMENT	HMA BIND CSE, N90, IL-19.0	POLY HMA BIND CSE, N105, IL-19.0	POLY HMA SURF CSE, MIX "E", N105	MATERIAL TRANSFER DEVICE	HMA SHOULDERS	SHLD REM & REPLACE 5"	BIT MATL (PC)	POLY BIT MATL (PC)	HMA SURF REM - BUTT JOINT	TEMP RAMP	SHOULDER RUMBLE STRIP	
NORTHBOUND	FEET	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	FOOT	GAL	GAL	SQ YD	SQ YD	FOOT	
UNION COUNTY (CONT)																			
RAMP F :																			
2986+47.71 TO 3008+19.99	2171.32							666.1	352.6	313.4	1332.15	459.35		260.6	965.6				2171
GORE AREA	9263 SQ FT											489.90		277.9					396
210' TAPER	210.00							24.0	38.1	37.5	99.6	58.0		65.1	65.1	106.6	35.5		420
RAMP A :																			
2994+56.59 TO 3002+99.31	840.00							269.2	138.3	122.9	530.4	444.3		252.0	296.3				840.00
GORE AREA	1433 SQ FT											75.8		43.0					409
3002+99.31 TO INLAT AT BASE OF RAMP	707.00							14.9	86.3	96.4	197.6	169.5		84.8	198.7	115.6	20.7		1414
INLAY AT BASE OF RAMP	2333 SQ FT			260.0															
RAMP B :																			
3020+29.85 TO 3025+13.27	479.00							119.9	63.5	56.4	239.8	253.3		143.7	136				479.00
GORE AREA	721 SQ FT											38.1		21.6					180
3020+29.85 TO INLAT AT BASE OF RAMP	1019.00							14.9	127.1	137.2	279.2	239.4		122.3	286	115.6	20.7		2038
SN 091-0020 INLAY	2063 SQ FT			229.2															
INLAY AT BASE OF RAMP				358.8															
UNION COUNTY SUBTOTALS		8480	112	848	934	49674	46954	24376	7217	6645	34355	14691	20283	8518	15750	1183	77		43787
PULASKI COUNTY																			
STAGE A																			
0+00 TO 66+00 RT	6600.00	2933.3						1,314.1											
5" SHLD REM & REPLACE																			
0+00 TO 66+00 LT RT	6600.00												6600.00						
MAINLINE																			
0+00.00 TO 63+90.00	6390.00					17,040.00	17,040.00	6,918.2	2,147.0	1,908.5	10973.76	4731.44		2683.80	4600.8				12780
63+90.00 TO 66+00.00	210.00							41.2	42.8	61.2	145.20	84.70		65.10	111.6	168.9			420.00
PULASKI COUNTY SUBTOTALS		2934	0	0	0	17040	17040	8274	2190	1970	11119	4817	6600	2749	4713	169	0		13200
PROJECT TOTALS		11414	112	848	934	66714	63,994	32,650	9,407	8,615	45474	19508	26883	11267	20463	1352	77		56987