

LOCATION OF PROJECT: FAP 0559 IL RTE 58 (GOLF ROAD) AT NEW WILKE ROAD, COOK COUNTY
 FUNDS: NEW WILKE RD - 75%FED(STP/STU) 25%LOCAL(ERP), GOLF RD - STP/STU 75%FED 25%LOCAL, URBAN
 CONSTRUCTION TYPE CODE 0003

CODE NO	DESCRIPTION	UNIT	TOTAL QUANTITY
* 88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	10
* 88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	2
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	32
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	25
* 88600700	PREFORMED DETECTOR LOOP	FOOT	2402
* 88700200	LIGHT DETECTOR	EACH	6
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	14
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	3438
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2
* 89502380	REMOVE EXISTING HANDHOLE	EACH	12
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	10
* 89502500	REMOVE TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1
* A2004815	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2" CALIPER, BALLED AND BURLAPPED	EACH	9
* A2008116	TREE, TILIA CORDATA GREENSPIRE (GREENSPIRE LITTLE LEAF LINDEN), 2" CALIPER, BALLED AND BURLAPPED	EACH	9
* C2000536	SHRUB, ARONIA MELANOCARPA (BLACK CHOKE BERRY), 3' HEIGHT, BALLED AND BURLAPPED	EACH	9
* C2005824	SHRUB, RHUS AROMATICA GRO-LOW (GRO-LOW FRAGRANT SUMAC), 2" WIDTH, CONTAINER	EACH	9
X0322836	REMOVE EXISTING FLARED END SECTION	EACH	2
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	20207
X8022712	CATCH BASINS, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	5
X8023508	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	6

Δ 0042 * SPECIALTY ITEM

CODE NO	DESCRIPTION	UNIT	TOTAL QUANTITY
X8026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	1
X8026622	VALVE VAULTS TO BE REMOVED	EACH	1
X8028510	CATCH BASINS, TYPE C, WITH SPECIAL FRAME AND GRATE	EACH	3
X7010218	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
* XE570228	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2
* X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	3141
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1456
* XZ127902	RETAINING WALL, SPECIAL	SQ FT	1220
Z600521E	HOT-MIX ASPHALT STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SQ YD	70
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	582
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0019600	DUST CONTROL WATERING	UNIT	15
Z0000240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	16
Z0030240	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	14
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	60
* Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	2
Z0058608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	719
Z0058610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	46
Z0058624	STORM SEWER (WATER MAIN REQUIREMENTS) 42 INCH	FOOT	126
Z0062466	TEMPORARY PAVEMENT	SQ YD	8839
* Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2
Δ Z0076800	TRAINEES	HOUR	1500
Δ Z0078804	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1500
* X8760055	PEDESTRIAN PUSH-BUTTON POST, TYPE A	EACH	2

FILE NAME: ...

DESIGNED - BLL	REVISED -
DRAWN - PMM	REVISED -
CHECKED - JGS	REVISED -
DATE - 8/06/12	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

IL RTE 58 (GOLF ROAD) AND NEW WILKE ROAD IMPROVEMENTS
 SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 5 OF 5 SHEETS STA. TO STA.

F.A.P. RTE. 0559	SECTION 00-00078-00-CH	COUNTY COOK	TOTAL SHEETS 116	SHEET NO. 7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 83735	