

SUMMARY OF QUANTITIES

	CODE NO	ITEM DESCRIPTION	UNITS	QUANTITY
				0021
	20101200	TREE ROOT PRUNING	EACH	2
	20200100	EARTH EXCAVATION	CU YD	797
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6,812
*	21400100	GRADING AND SHAPING DITCHES	FOOT	583
	25000100	SEEDING, CLASS 1	ACRE	1.4
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	127
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	127
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	127
	25100125	MULCH, METHOD 3	ACRE	1.4
	35101400	AGGREGATE BASE COURSE, TYPE B	TON	704
	40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	3
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	43
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	20,689
*	42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1,985
*	42400800	DETECTABLE WARNINGS	SQ FT	469
*	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	361
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	45
	44000600	SIDEWALK REMOVAL	SQ FT	1,106
*	44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	40
*	56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	3
	60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	110
	60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	45
	67100100	MOBILIZATION	L SUM	1
*	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
*	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
#	78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	984
#	78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	54
*	Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	132

SPECIALTY ITEMS
* SEE SPECIAL PROVISIONS

Plotlet: July 31, 2012 @ 3:25 PM By: Larry Nelson - Tab: 03 S00 22x34

COPYRIGHT © 2012 ENGINEERING ENTERPRISES, INC.

Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60554
630.466.6700 / www.eeiweb.com

UNITED CITY OF YORKVILLE
800 GAME FARM ROAD
YORKVILLE, IL 60560

1	7/31/12	REVISED PER IDOT COMMENTS	
NO.	DATE	REVISIONS	

SAFE ROUTES TO SCHOOL
UNITED CITY OF YORKVILLE
KENDALL COUNTY, ILLINOIS

SUMMARY OF QUANTITIES

DATE:	MAY 2012
PROJECT NO:	Y01114
FILE:	Y01114-CVR
SHEET	3 OF 12

Path: \\S056R003\Y01114-C30\DWG\DWG_FINAL_ENG\Y01114-CVR