

GENERAL NOTES

NO UTILITY CONFLICTS ARE ANTICIPATED AS A PART OF THIS PROJECT, HOWEVER THE ENGINEER AND OWNER FURTHER DO NOT WARRANT THAT ALL UTILITIES HAVE BEEN ILLUSTRATED ON THESE DOCUMENTS. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR CONTACTING J.U.L.I.E. FOR FIELD VERIFICATION OF ALL UTILITIES ON THE SITE PRIOR TO COMMENCEMENT OF CONSTRUCTION. IF THE CONTRACTOR DETERMINES THAT SUBSTANTIAL DISCREPANCY EXISTS BETWEEN FIELD VERIFIED UTILITIES AND THESE PLANS WHICH WOULD SIGNIFICANTLY AFFECT THE FUNCTION, COST, OR PERFORMANCE OF THE PROJECT, THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE ENGINEER FOR CLARIFICATION AND PROJECT DIRECTION.

ALL TRAFFIC CONTROL INCLUDING BUT NOT LIMITED TO, WORK ZONE, TEMPORARY, AND PERMANENT, SHALL BE FURNISHED, INSTALLED, MAINTAINED, RELOCATED, AND/OR REMOVED ACCORDING TO SECTION 700 OF THE LATEST EDITION OF THE IDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

TRAFFIC CONTROL SIGNS SHALL BE 48" FLUORESCENT ORANGE.

THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE VILLAGE OF GLEN CARBON AT LEAST FORTY-EIGHT (48) HOURS IN ADVANCE PRIOR TO COMMENCEMENT OF ANY CONSTRUCTION ACTIVITIES OR WORK REQUIRING INSPECTION OR APPROVAL BY THE AFFECTED UNITS OF GOVERNMENT.

SUMMARY OF QUANTITIES

Pay Item No.	Pay Item	Unit	Pay Item Total:
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	133
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	165
40600300	AGGREGATE (PRIME COAT)	TON	20
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	14
40600990	TEMPORARY RAMP	SQ YD	115
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,260
40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	108
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	3
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	7
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	597
42400800	DETECTABLE WARNINGS	SQ FT	103
44000100	PAVEMENT REMOVAL	SQ YD	110
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	14,543
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	31
44000400	GUTTER REMOVAL	FOOT	46
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	123
44000600	SIDEWALK REMOVAL	SQ FT	577
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	6
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	33
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	47
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	13,105
60260100	INLETS TO BE ADJUSTED	EACH	1
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	37
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	94
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	885
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	325
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	220
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	49
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15,727
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	191
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	60
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1

* SPECIALTY ITEM

**THOUVENOT,
WADE &
MOERCHEN, INC.**
ENGINEERS ♦ SURVEYORS ♦ PLANNERS



CORPORATE OFFICE
4940 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6688
corp@twm-inc.com

WATERLOO OFFICE
113 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 939-5050
FAX (618) 939-3938
waterloo@twm-inc.com

EDWARDSVILLE OFFICE
600 COUNTRY CLUB VIEW, SUITE 1
EDWARDSVILLE, ILLINOIS 62025
TEL (618) 656-4040
FAX (618) 656-4343
edwardsville@twm-inc.com

ST. LOUIS OFFICE
720 OLIVE ST., SUITE 200 A
ST. LOUIS, MISSOURI 63101
TEL (314) 241-6300
stlouis@twm-inc.com

PROFESSIONAL REGISTRATIONS	LICENSE NO.
ILLINOIS PROFESSIONAL DESIGN FIRM	181-001220
PROFESSIONAL ENGINEERING CORP.	62-053710
PROFESSIONAL STRUCTURAL ENGR. CORP.	81-052602
ILLINOIS PROF. LAND SURVEYING CORP.	048-000020
MISSOURI PROFESSIONAL ENGR. CORP.	NC 091528
MISSOURI LAND SURVEYING CORP.	NC 000346

SEAL

This Professional Service conforms to the current Illinois Minimum Standards for a Boundary Survey

Signature: _____
Expiration Date: _____

STATEMENT OF RESPONSIBILITY
I hereby confirm that the document herein to be authorized by my seal is restricted to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be utilized for any other part of the architectural, engineering or survey project.

**GENERAL NOTES AND
SUMMARY OF QUANTITIES**

PROJECT: SECTION 10-00018-02-RS
GLEN CARBON ROAD RESURFACING
VILLAGE OF GLEN CARBON
MADISON COUNTY, ILLINOIS

REV	DATE	DESCRIPTION
△		
△		
△		

DRAWN BY:	PDH	SHEET
DESIGNED BY:	MJK	2
CHECKED BY:	MJK	
APPROVED BY:	MJK	
PROJECT NUMBER	T19080125B	
<input checked="" type="checkbox"/> ISSUED FOR REVIEW	<input type="checkbox"/> ISSUED FOR BIDDING	
<input type="checkbox"/> ISSUED FOR CONSTR.	<input type="checkbox"/> RECORD DRAWING	