



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 29, 2012

SUBJECT: Various Routes
Project SRTS-4009(032)
Section 10-00004-00-SW (Goreville)
Johnson County
Contract No. 99447
Item 084
November 9, 2012 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

1. Page 5 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with the initials "P.E." written in a smaller font to the right.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

CONCRETE STRUCTURES: Concrete structures shall include the steps, handicapped accessible ramps and the new headwalls located at the Hwy 37 and Collins Str. Intersection. Construction of the structures shall include the required reinforcement for concrete at each location in accordance with Illinois Department of Transportation. Contractor's pricing shall include all necessary forms, labor and other appurtenances required to perform the work as shown on the plans. Concrete compressive strength used in the structures shall be 4000 psi. Contractor will be responsible for concrete compressive strength tests, including the cost of testing.

BASIS OF PAYMENT: This work will be paid for at the contract unit price per (CU. YD.) for CONCRETE STRUCTURES.

SPLIT RAIL FENCE: Split rail fence shall be fabricated from galvanized steel pipe, 17 gauge thickness. End post shall be 2 3/8" diameter, 17 gauge, line posts shall be 1 5/8" diameter, 17 gauge, and top & middle rail shall be 1 5/8 diameter, 17 gauge. Fence shall be a 2-rail fence profile. Rail posts shall be 6' long with 2-holes each for fence railing. Fence rails shall be 10' in length on center. Installation of fence shall be in accordance with the manufactures recommendations. Fence shall be installed at the locations shown on the plans. **Split rail fence shall be manufactured by Terrace Fence Company or equal.** Installation shall be in accordance with the manufacturer's directions.

Contractor shall also provide and install concrete anchors around fence posts as required by the manufacture.

BASIS OF PAYMENT: This work will be paid for at the contract unit price per (FOOT) for SPLIT RAIL FENCE.

Revised 10/29/12