

F.A. RTE.	SECTION	COUNTY	TOTAL SHEET SHEETS	NO.
Hwy 37 & COLLINS	10-00004-00-SN	JOHNSON	15	2

NOTES:

SUMMARY OF QUANTITIES


1. ALL MATERIALS AND METHODS SHALL BE IN ACCORDANCE WITH STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS LATEST EDITION.
2. CONTRACTORS SHALL CONTACT EACH UTILITY COMPANY PRIOR TO CONSTRUCTION. ANY DAMAGE CAUSED TO EXISTING UTILITIES SHALL BE THE CONTRACTORS RESPONSIBILITY AND CONTRACTOR SHALL LEND ALL POSSIBLE ASSISTANCE IN RESTORING SERVICE.
3. NOT ALL OF THE GAS, POWER OR TELEPHONE LINES, WERE ABOVE OR BELOW GROUND, HAVE BEEN SHOWN ON THE PLANS. THE LOCATION OF EXISTING UNDERGROUND UTILITIES, SUCH AS GAS OR WATER MAINS, ETC., AS SHOWN ON THE PLANS HAVE BEEN DETERMINED FROM THE BEST AVAILABLE INFORMATION AND ARE GIVEN FOR THE CONVENIENCE OF THE CONTRACTOR. THE CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR ALL UTILITIES, WHETHER SHOWN OR NOT, AND MUST REALIZE THAT THE ACTUAL LOCATIONS AND THOSE SHOWN MAY BE DIFFERENT.
4. INTERRUPTION OF UTILITY SERVICE IS NOT EXPECTED. HOWEVER, IF INTERRUPTION OF ANY UTILITY SERVICE IS NECESSARY, THE CONTRACTOR SHALL GIVE AT LEAST ONE DAY NOTICE TO CUSTOMERS INVOLVED AND SHALL USE ALL HIS RESOURCES TO MINIMIZE INTERRUPTION.
5. ALL DISTURBED AREAS SHALL BE GRADED TO PROVIDE POSITIVE DRAINAGE. CULVERTS, FIELD TILES AND OTHER DRAINAGE FACILITIES DAMAGED DURING CONSTRUCTION SHALL BE REPLACED BY CONTRACTOR AT NO ADDITIONAL COST TO THE VILLAGE.
6. ANY PERMANENT SURFACE, STREET, DRIVEWAY, OR SIDEWALK DAMAGE BY CONTRACTOR SHALL BE REPAIRED BY CONTRACTOR.
7. DETECTABLE WARNINGS SHALL BE YELLOW IN COLOR AT ALL LOCATIONS.

CODE #	ITEM DESCRIPTION	TOTAL	UNIT
20100110	TREE REMOVAL (6 - 15 UNIT DIAMETER)	100	UNIT
20200100	EARTH EXCAVATION	300	CU YD
21400100	GRADING AND SHAPING DITCH	400	FOOT
25000100	SEEDING, CLASS I	0.9	ACRE
28100107	STONE RIP RAP CLASS A 4	600	SQ YD
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	4011	SQ FT
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	524	SQ FT
42400800	DETECTABLE WARNINGS	256	SQ FT
44000300	CURB REMOVAL	98	FOOT
44000600	SIDEWALK REMOVAL	1401	SQ FT
50300225	CONCRETE STRUCTURES	28	CU YD
50901760	PIPE HANDRAIL	240	FOOT
54010604	PRE CAST CONCRETE BOX CULVERT, 6'x4'	24	FOOT
542A0220	PIPE CULVERT CL A 1, 15"	20	FOOT
67100100	MOBILIZATION	1	LUMP SUM
70100450	TRAFFIC CONTROL AND PROTECTION	1	LUMP SUM
72000100	SIGN PANEL TYPE I	144	SQ FT
72400500	RELOCATE SIGN PANEL ASSEMBLY	3	EACH
72900100	METAL POST TYPE A	168	FOOT
Δ 78001150	PAINT PAVEMENT MARKING LINE 12"	1344	FOOT
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	2	EACH
42300100	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 5 INCH	16.3	SQ YD
XX000503	SPLIT RAIL FENCE	680	FOOT
Δ X0325714	FLASHING BEACON POST MOUNTED, SOLAR POWERED INSTALLATION	6	EACH

**Δ SPECIALTY ITEMS**

NO.	DESCRIPTION	BY	DATE	NO.	DESCRIPTION	BY	DATE
					DESIGNED		
					DRAWN	WFL	3/27/12
					CHECKED	JHC	3/27/12
				A1	REVISED PER IDOT REQUEST	WDS	7/30/12

VILLAGE OF GOREVILLE  
JOHNSON COUNTY, IL  
SAFE ROUTES TO SCHOOL  
NOTES AND QUANTITIES



**JOHN H. CRAWFORD & ASSOCIATES, P.C.**  
CIVIL ENGINEERS, LAND SURVEYORS  
201 SOUTH DIVISION STREET, CARTERSVILLE, ILLINOIS 62918  
PHONE (618) 985-8370 FAX (618) 985-4092  
PROFESSIONAL DESIGN FIRM # 184-002885

SHEET NO.	
2	
ISSUE	DATE
A1	7/30/12