

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 344	540 R-PCC-PP-1	COOK	19	10

CONTRACT 60C41

EASTBOUND IL 83

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2			MEDIAN CROSSOVER*	
		SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)	TYPE	SIZE (L X W)	AREA (SQ. YD.)
26	736+30	10 x 12	13.3	TYPE II	10 x 12	13.3	TYPE II	x	
27	736+50	28 x 12	37.3	TYPE IV	12 x 12	16.0	TYPE III	x	
28	737+10	x			16 x 12	21.3	TYPE III	x	
29	737+97	x			6 x 12	8.0	TYPE II	x	
30	739+16	12 x 12	16.0	TYPE III	x			x	
31	740+84	10 x 12	13.3	TYPE II	12 x 12	16.0	TYPE III	x	
32	741+34	11 x 12	14.7	TYPE II	12 x 12	16.0	TYPE III	x	
33	741+74	x			6 x 12	8.0	TYPE II	x	
34	743+50	6 x 12	8.0	TYPE II	6 x 12	8.0	TYPE II	x	
35	746+50	36 x 12	48.0	TYPE IV	36 x 12	48.0	TYPE IV	x	
36	746+83	x			12 x 12	16.0	TYPE III	x	
37	748+16	16 x 12	21.3	TYPE III	12 x 12	16.0	TYPE III	x	
38	748+18	12 x 12	16.0	TYPE III	12 x 12	16.0	TYPE III	x	
39	748+38	x			38 x 12	50.7	TYPE IV	x	
40	748+96	x			12 x 12	16.0	TYPE III	x	
41	749+27	5 x 12	6.7	TYPE II	15 x 12	20.0	TYPE III	x	
42	749+44	x			8 x 12	10.7	TYPE II	x	
43	749+85	10 x 12	13.3	TYPE II	10 x 12	13.3	TYPE II	x	
44	750+38	x			9 x 12	12.0	TYPE II	x	
45	750+59	21 x 12	28.0	TYPE IV	21 x 12	28.0	TYPE IV	x	
46	750+72	x						90 x 4	40.0
47	750+86	15 x 12	20.0	TYPE III	18 x 12	24.0	TYPE III	x	
48	753+50	21 x 12	28.0	TYPE IV	21 x 12	28.0	TYPE IV	x	
49	755+13	x			x			10 x 4	4.4
50	755+25	21 x 12	28.0	TYPE IV	18 x 12	24.0	TYPE III	x	

1. CENTERLINE OF HIGGINS RD: STA. 718+76

* MEDIAN REMOVAL, CORRUGATED MEDIAN

2. CENTERLINE OF I-90 BRIDGE: STA. 725+33

3. CENTERLINE OF ELMHURST RD: STA. 768+05

ILLINOIS DEPARTMENT OF TRANSPORTATION

**IL ROUTE 83 (OAKTON ST.)
PAVEMENT PATCHING SCHEDULE**