

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2678	N-7-5-I-1	COOK	18	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 60C45

INDEX OF SHEETS

SHEET NO.	DESCRIPTION	STANDARD NO.
1	COVER SHEET	701411-03
2	INDEX OF SHEETS, LIST OF STATE STANDARDS AND GENERAL NOTES	701601-04
3	SUMMARY OF QUANTITIES	
4	TRAFFIC CONTROL AND PROTECTION STAGE I	702001-06
5	TRAFFIC CONTROL AND PROTECTION STAGE II	
S.N. 016-0678		
6	GENERAL PLAN & ELEVATION	
7	CONSTRUCTION STAGING TYPICAL SECTIONS	
8	CROSS SECTION	
9	DECK CONCRETE PATCHING	
10	SILICONE SEAL JOINT REPAIR	
11	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) (TC11)	
12	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC13)	
13	ISTHA STANDARD: CONSTRUCTION SIGNS (E1-00)	
14	ISTHA STANDARD: CONSTRUCTION SIGNS (E1-00)	
15	ISTHA STANDARD: LANE CLOSURE DETAILS (E2-00)	
16	ISTHA STANDARD: LANE CLOSURE DETAILS (E2-00)	
17	ISTHA STANDARD: LANE CLOSURE DETAILS (E2-00)	
18	ISTHA STANDARD: TEMPORARY GORE DETAILS AND SHOULDER CLOSURE DETAILS (E3-00)	

LIST OF STATE STANDARDS

STANDARD NO.	DESCRIPTION
701411-03	LANE CLOSURE, MULTILANE AT ENTRANCE OR EXIT RAMP FOR SPEED \geq 45 MPH
701601-04	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
702001-06	TRAFFIC CONTROL DEVICES

GENERAL NOTES:

1. THESE PLANS HAVE BEEN PREPARED FROM NOTES RECEIVED FROM I.D.O.T. FIELD MAINTENANCE ENGINEERS.
2. ALL PAVEMENT MARKINGS AND RAISED REFLECTORS AFFECTED BY THE BRIDGE REPAIRS SHALL BE REPLACED. NOMINAL QUANTITIES HAVE BEEN INCLUDED IN THE CONTRACT FOR THIS WORK.
3. THE COST OF THE TOLLWAY PERMIT AND BOND AND THE COST OF THE TRAFFIC CONTROL AND PROTECTION ON THE NORTHWEST TOLLWAY TO INSTALL AND REMOVE THE PROTECTIVE SHIELDING SHALL BE INCLUDED IN THE BID PRICE FOR TRAFFIC CONTROL AND PROTECTION (SPECIAL).
4. PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT BID PRICE FOR THE WORK.
5. ALL TRAFFIC CONTROL DEVICES AND MEASURES DEEMED NECESSARY AND PLACED IN ACCORDANCE WITH THE APPLICABLE PORTIONS OF THE VARIOUS STANDARDS SHOWN ON THE TITLE SHEET WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE PAY ITEM "TRAFFIC CONTROL AND PROTECTION".
6. THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847)705-4470 AT LEAST 72 HOURS PRIOR TO INSTALLATION OF THE TEMPORARY TRAFFIC CONTROL DEVICES.
7. THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
8. DO NOT SCALE THESE PLANS FOR CONSTRUCTION PURPOSES
9. WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR MUST EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND TO THE ADJOINING RESIDENTIAL AREAS.

SCOPE OF WORK:

1. REMOVE THE EXISTING 2" HOT-MIX ASPHALT SURFACE & HYDRO-SCARIFY 1/2" OF THE CONCRETE SURFACE
2. MARK AREAS OF FULL DEPTH REPAIRS
3. PERFORM DECK SLAB REPAIRS
4. REPAIR SILICONE JOINT SEAL
5. PLACE A 2 1/2" LATEX CONCRETE OVERLAY

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS,
LIST OF STATE STANDARDS
AND GENERAL NOTES
F.A.U. RTE. 2678 / ELMHURST ROAD

SCALE: NONE
DATE: JULY 25, 2007

DRAWN BY: F.M.
CHECKED BY: B.N.S.

CHRISTIAN-ROGE & ASSOC., INC.
CHICAGO ILLINOIS