

F.A.P. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2007-014DM	LAKE	18	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* F.A.P. 337 F.A.P. 432 F.A.P. 870		CONTRACT NO. 60C51		

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	COVER SHEET
2	LOCATION DESCRIPTIONS
3	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
4	SUMMARY OF QUANTITIES
5-7	DEMOLITION PLAN
8-10	LANDSCAPING PLAN
11	BUILDING ASBESTOS LOCATION DETAILS (FOR INFORMATION ONLY)
12	EROSION CONTROL PLAN
13-15	RIGHT-OF-WAY PLAT OF HIGHWAYS (FOR INFORMATION ONLY)
16	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
17	SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS
18	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS

LIST OF STANDARDS

000001-04 STANDARD SYMBOLS, ABBREVIATION AND PATTERNS
 701101-01 OFF-ROAD OPERATION, MULTILANE LESS THAN 4.5m (15') AWAY FOR SPEEDS > 45 MPH
 701106-01 OFF-ROAD OPERATION, MULTILANE MORE THAN 4.5m (15') AWAY FOR SPEEDS > 45 MPH
 702001-00 TRAFFIC CONTROL DEVICES

GENERAL NOTES PERTAINING TO LOCATION 1 (14736 AND 14746 HALF DAY RD., LINCOLNSHIRE)

FILL ON THE PROPERTY MUST BE LIMITED IN HEIGHT TO MATCH THE EXISTING GRADE DUE TO THE PROPERTY BEING LOCATED IN A SPECIAL FLOOD HAZARD AREA AS WELL AS A FLOODWAY.

THE CONTRACTOR MUST CONTACT THE LAKE COUNTY DEPARTMENT OF HEALTH TO OBTAIN A PERMIT AND SPECIFICATION FOR THE REMOVAL OF THE SEPTIC TANKS.

THE CONTRACTOR MUST CONTACT THE VILLAGE OF LINCOLNSHIRE DEPARTMENT OF PUBLIC WORKS AT (847) 883-8600 ext. 2100 FOR WATER SERVICE DISCONNECTION REQUIREMENTS.

ALL EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE PROCEDURES AND STANDARDS FOR URBAN SOIL EROSION AND SEDIMENTATION CONTROL AND THE LAKE COUNTY STORM WATER MANAGEMENT COMMISSION'S TECHNICAL REFERENCE MANUAL.

SOIL DISTURBANCE SHALL BE CONDUCTED IN SUCH A MANNER AS TO MINIMIZE EROSION. SOIL STABILIZATION MEASURES SHALL CONSIDER THE TIME OF YEAR, SITE CONDITIONS, AND THE USE OF TEMPORARY OR PERMANENT MEASURES.

SOIL EROSION AND SEDIMENTATION CONTROL FEATURES SHALL BE CONSTRUCTED PRIOR TO THE COMMENCEMENT OF UPLAND DISTURBANCE.

TEMPORARY SOIL STABILIZATION SHALL BE APPLIED TO DISTURBED AREAS WITHIN 14 CALENDAR DAYS OF THE END OF THE ACTIVE HYDROLOGIC DISTURBANCE. PERMANENT STABILIZATION SHALL BE DONE WITHIN 14 DAYS AFTER COMPLETION OF THE FINAL GRADING OF THE SOIL.

ALL STORM SEWER FACILITIES THAT ARE OR WILL BE FUNCTIONING DURING CONSTRUCTION SHALL BE PROTECTED, FILTERED, OR OTHERWISE TREATED TO REMOVE SEDIMENT.

ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER TEMPORARY MEASURES ARE NO LONGER NEEDED. TRAPPED SEDIMENT AND OTHER DISTURBED SOIL AREAS SHALL BE PERMANENTLY STABILIZED.

ALL TEMPORARY AND PERMANENT EROSION CONTROL MEASURES MUST BE MAINTAINED AND REPAIRED AS NEEDED. THE GENERAL CONTRACTOR WILL BE RESPONSIBLE FOR INSPECTION AND REPAIR DURING CONSTRUCTION. THE OWNER WILL BE RESPONSIBLE IF EROSION CONTROL IS REQUIRED AFTER THE CONTRACTOR HAS COMPLETED THE PROJECT.

THE EROSION CONTROL MEASURES INDICATED ON THE PLANS ARE THE MINIMUM REQUIREMENTS. ADDITIONAL MEASURES MAY BE REQUIRED, AS DIRECTED BY THE ENGINEER OR GOVERNING AGENCY.

THE COST OF OBTAINING A PERMIT FROM THE VILLAGE OF LINCOLNSHIRE FOR USE OF THE HIKING AND RECREATIONAL PATH AND ITS RESTORATION SHALL BE INCLUDED IN THE COST OF BUILDING REMOVAL.

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-893-0123 OR FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)

THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING A DEMOLITION PERMIT FROM THE VILLAGES OF LINCOLNSHIRE, MUNDELEIN AND GLEN ELLYN.

THE CONTRACTOR MUST CONTACT THE VILLAGES OF LINCOLNSHIRE, MUNDELEIN, AND GLEN ELLYN FOR CORRESPONDING UTILITY DISCONNECTION REQUIREMENTS.

THE CONTRACTOR COORDINATE CONSTRUCTION ACTIVITIES UTILITY COMPANIES AND THE VILLAGES OF LINCOLNSHIRE, MUNDELEIN, AND GLEN ELLYN.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SANDBAGS ON EACH TYPE I OR TYPE II BARRICADE USED AND ONE (1) WEIGHTED SANDBAG ACROSS EACH BOTTOM RAIL.

BACKFILL USED FOR ANY HOLES, SUCH AS BASEMENTS, SHALL BE FILLED WITH POROUS GRANULAR EMBANKMENT AND SHALL BE INCLUDED IN THE COST OF BUILDING REMOVAL.

ALL TRAFFIC CONTROL SHALL BE INCIDENTAL TO THIS CONTRACT.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 INDEX OF SHEETS, STATE STANDARDS,
 AND GENERAL NOTES
 IL. 22 (HALF DAY RD.), YORK CT., &
 IL. 53 (S. COLUMBUS AVE.)
 BUILDING DEMOLITION

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY: P. STEED
 CHECKED BY: _____