F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3597	07101-1	COOK	11	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT 60D24

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: URBAN 100% STATE SFTY-2A					
50102400	CONCRETE REMOVAL	CU YD	6.1	6.1					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	5	5					
50300260	BRIDGE DECK GROOVING	SQ YD	38.4	38.4					
50300300	PROTECTIVE COAT	SQ YD	81.6	81.6					
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	414.8	414.8					
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	320	320					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2080	2080					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2					
67100100	MOBILIZATION	L SUM	1	1					
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1					
7010 1800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	150	150					
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	150	150					
X0301424	SILICONE JOINT SEALER	FOOT	24	24					
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	414.8	414.8					
X0321781	MECHANICAL SPLICE	EACH	135	135					
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48					
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	56.3	56.3					
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PLOT DATE: 9/5/2007

Rev.

9/5/2007