

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
370	01031-2	COOK	27	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		X281-24 STATE 100%				
X0325804	BRIDGE APPROACH PAVEMENT REMOVAL	SQ YD	720	720				
20200100	EARTH EXCAVATION	CU YD	412	412				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	271	271				
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	210	210				
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	396	396				
42001500	P. C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SQ YD	149	149				
42100360	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 13"	SQ YD	240	240				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1200	1200				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	240	240				
44000600	SIDEWALK REMOVAL	SQ FT	1200	1200				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	107	107				
50300260	BRIDGE DECK GROOVING	SQ YD	499	499				
50300300	PROTECTIVE COAT	SQ YD	1588	1588				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16080	16080				
50800515	BAR SPLICERS	EACH	506	506				
50901755	PARAPET RAILING, SPECIAL	FOOT	162	162				
51500100	NAME PLATES	EACH	1	1				
59000200	EPOXY CRACK INJECTION	FOOT	20	20				
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2				
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	25	25				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5				
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2891	2891				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	963	963				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	222	222				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	222	222				
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	101	101				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		X281-24 STATE 100%				
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	52	52				
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10	10				
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	10	10				
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	499	499				
50101500	REMOVAL OF EXISTING SUPERSTRUCTURE	EACH	1	1				
XX003515	PRECAST PRESTRESSED CONCRETE DECK BEAMS (42" DEPTH)	SQ FT	5290	5290				
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	44	44				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	11	11				

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
WESTERN AVE./GREGORY ST.  
OVER VERMONT AVE.

8/29/2007 8:10:00 AM C:\projects\62362\sum\_r.dwg