CONTRACT NO. 64237

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*2079	------**------	CARROLL & OGLE	232	8
STA. _____	TO STA. _____			
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

80% FED.
20% STATE

	CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	1000-1A COUNTY CARROLL	1000-1A COUNTY OGLE	SFTY-2A COUNTY OGLE	Y030-1E COUNTY CARROLL	Y031-1F *(US 52) **(16,17,18)RS-3 & (16BR)M-1 COUNTY CARROLL	COUNTY OGLE
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	80	7	73				
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14,411	1,241	13,170				
	70300610	TEMPORARY PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	250	250					
	70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	49,031	22,991	26,040				
	70300640	TEMPORARY PAINT PAVEMENT MARKING LINE 8"	FOOT	930	930					
	70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	638	545	93				
	70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	112	60	52				
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1201	103	1098				
*	72000100	SIGN PANEL - TYPE 1	SQ FT	27					27	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	125	125					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18,290	11,496	6,794				
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	465	465					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	319	272	47				
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	143	30	113				
*	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	202,671	560	202,111				
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	185	96	89				
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	32		32				
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1				1		
*	81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	43				43		
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	30				30		
*	82104000	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 400 WATT	EACH	2				2		
*	82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1				1		
*	83035300	LIGHT POLE, STEEL, 40 FT. M.H., TENON MOUNT - TWIN	EACH	2				2		
*	83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8"x8'	EACH	1				1		
*	83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	4				4		
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6				6		
*	A2001714	TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	7	3	4				
*	A2002914	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	7	3	4				
*	A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	8	3	5				
*	B2000562	TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 4' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	15	5	10				
*	B2004814	TREE, MALUS SARGENTII (SARGENT CRABAPPLE) 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	15	5	10				

* SPECIALTY ITEM

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAS ROUTE 2079 (US 52)
SECTION (16,17,18)RS-3 & (16BR)M-1
CARROLL & OGLE COUNTIES

SCALE: VERT. HORIZ. DRAWN BY
DATE CHECKED BY

SUMMARY OF QUANTITIES

PLOT DATE = Fri Mar 09 06:03:56 2007
FILE NAME = c:\projects\d202685\d202685sov.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = dossedd