

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*2079	**	CARROLL & OGLE	232	32
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
(US 52)	**(16,17,18)RS-3 & (16BR)M-1			

EARTHWORK AND TOPSOIL SCHEDULE

EARTH WORK AND TOPSOIL SCHEDULE								
LOCATION	20200100			EMBANK (FILL) CU YD	EARTH WORK BALANCE WASTE (+) SHORTAGE (-) CU YD	TOP SOIL REQUIRED CU YD	21101505 X2110100	
	EARTH EXC (CUT) CU YD	EARTH EXC ADJ SHRINK 25% EARTH CU YD	TOP SOIL EXCAV & PLACE CU YD				TOP SOIL FURNISH & PLACE, SPECIAL CU YD	
	<i>Carrol County</i>							
<i>Mainline</i>								
1495+60 - 1513+15	10,812	8,109	1,269	6,840	1,129			
<i>Ogle County</i>								
<i>Mainline</i>								
0+00 - 11+50	3,467	2,600	1,310	1,290	708			
<i>Culverts</i>								
176+00 - 190+50	2,557	1,918	1,235	683	758			
201+00 - 205+50	732	549	586	-37	264			
323+00 - 331+00	4,212	3,159	167	2,992	392			
<i>SIDERoads</i>								
<i>Carrol County</i>								
<i>Brookville</i>								
117+50 - 131+00	23,667	17,750	3,038	14,712	2,586	4,893		
<i>Brookville (PE)</i>								
800+50 - 802+25	431	323	0	323				
<i>Brookville (FE)</i>								
820+25 - 822+00	1,912	1,434	70	1,364				
<i>IL 64</i>								
1508+50 - 1511+16	2,105	1,579	417	1,162	156			
<i>Ogle County</i>								
<i>IL 64</i>								
0+00 - 4+50	2,534	1,901	14	1,887	197			
<i>Eldorado</i>								
597+75 - 600+50	264	198	42	156	59			
<i>Ogle</i>								
158+00 - 163+00	5,098	3,824	284	3,540	300			
<i>Taylor</i>								
998+25 - 999+75	951	713	1	712	72			
<i>Carrol County Totd</i>	38,926	29,195	4,794	24,401	3,871	3,871	0	
<i>Ogle County Totd</i>	19,815	14,861	3,639	11,222	2,750	1,022	1,728	
TOTAL	58,741	44,056	8,433	35,623	6,621	4,893	1,728	

PLOT DATE = Wed Mar 07 13:48:05 2007
 FILE NAME = c:\p\proj\161718\161718\161718\161718.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = dmsd

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAS ROUTE 2079 (US 52)
SECTION (16,17,18)RS-3 & (16BR)M-1
CARROLL & OGLE COUNTIES
 SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE